

**ADDENDUM 2: INVITATION FOR BIDS
BRECKENRIDGE DRIVE DRAINAGE
IMPROVEMENTS #25-20250613**

THE BID OPENING DATE HAS BEEN EXTENDED TO JULY 28, 2025 – 1:00PM EST

CLARIFICATIONS

1. The following items have no specification reference and thusly the work within each scope is unknown:

- 58 As-Built Survey - - 1 LS
- 59 Post-Construction CCTV - - 1 LS
- 60 Geotechnical Services - - 1 LS
- 61 Road Replacement - - 1 LS

Response from the Town:

*These lines have been updated to allowances. **See revised Unit Price Bid Schedule.***

- 43 Level A Subsurface Utility Exploration - \$15,000
- 44 Utility Coordination - \$15,000
- 58 As-Built Survey - \$20,000
- 59 Post-Construction CCTV - \$10,000
- 60 Geotechnical Services - \$15,000

Clarification on 61 Road Replacement:

*Contractor to bid this item as a lump sum based on the following:
Use asphalt pavement section detail "Typ. Asphalt Pavement Schedule (Category 1)" in sheet C70 for full street pavement replacement within the R/W – see extent based on milling plan – sheet C20.*

2. There is no line item for the following scope of work shown on the plans:
8" ABC & S9.5A called for as "road replacement" on C70

Response from the Town: All section components lumped under "Road Replacement" bid item.

3. Please clarify if this item is to include the apron & driveway as shown on C50:
10 6" Portland Cement Concrete Pavement 210 SY

Response from the Town: This item pertains to the driveway's aprons only.

JULY 9, 2025



**RECEIPT OF ADDENDA ACKNOWLEDGEMENT
BRECKENRIDGE DRIVE DRAINAGE
IMPROVEMENTS #25-20250613**

The Bidder shall acknowledge receipt of Addendum 2, including the Revised Unit Price Bid Schedule, issued to this solicitation on July 9, 2025 by completing the information below. **This form must be submitted with the bid package.** Failure to acknowledge an addendum that has a material impact on this solicitation may negatively impact the responsiveness of your bid.

Bidder: _____

Authorized Signature: _____

Date: _____

REVISED

PROJECT NAME: Breckenridge Drive Drainage Improvements

MCADAMS PROJECT NO.: KND21001

DATE: May 28, 2025

ITEM NO.	DESCRIPTION	SPEC SECTION	PAY ITEMS PARAGRAPH	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	Traffic Control Measures	ToK 2.07	-	1	LS		
2	Asphalt Concrete Intermediate Course, Type I19.0B	ToK 3.03	-	180	TN		
3	Asphalt Concrete Intermediate Course, Type I19.0C	NCDOT 610	610-16	11	TN		
4	Asphalt Concrete Surface Course, Type S9.5B	ToK 3.03	610-16	110	TN		
5	Asphalt Binder for Plant Mix	ToK 3.03	620-4	25	TN		
6	Aggregate Base Course, Type B25.0B	ToK 3.03	545-6	55	TN		
7	Aggregate Base Course, Type B25.0C	NCDOT 610	610-16	40	TN		
8	Remove, Store, and Reset Mailboxes	ToK 3.07	-	4	EA		
9	1' - 6" Concrete Curb and Gutter	ToK 4.00	846-4	530	LF		
10	6" Portland Cement Concrete Pavement	ToK 4.01	710-10	210	SY		
11	24" Drainage Pipe, HDPP	ToK 5.02	305-4	595	LF		
12	Custom Reinforced Concrete Endwall	ToK 5.03	838-4	25	CY		
13	Drainage Structures, 0'-5' deep	ToK 5.03	840-4	7	EA		
14	Drainage Structures, 5'-15' deep	ToK 5.03	840-4	30	LF		
15	Frame with Grate and Hood	ToK 5.03	840-4	5	EA		
16	Manhole Ring and Cover	ToK 5.03	840-4	2	EA		
17	Rip Rap, Class I	ToK 5.04	876-4	25	TN		
18	Rip Rap, Class II	ToK 5.04	876-4	60	TN		
19	Clearing and Grubbing	NCDOT 200	200-8	1	LS		
20	Comprehensive Grading	NCDOT 226	226-3	1	LS		
21	Borrow Excavation	NCDOT 230	230-5	1,340	CY		
22	Removal of Existing Pavement	NCDOT 250	250-3	350	SY		
23	Foundation Conditioning Material, Minor Structures	NCDOT 300	300-9	370	TN		

REVISED

ITEM NO.	DESCRIPTION	SPEC SECTION	PAY ITEMS PARAGRAPH	QUANTITY	UNIT	UNIT PRICE	TOTAL
24	Foundation Conditioning Geotextile	NCDOT 300	300-9	790	SY		
25	Pipe Removal, 15" RCP	NCDOT 340	340-4	2	LF		
26	Pipe Removal, 24" RCP	NCDOT 340	340-4	48	LF		
27	Pipe Removal, 42" RCP	NCDOT 340	340-4	7	LF		
28	Removal of Existing Structure	NCDOT 402	402-3	1	LS		
29	Fine Grading	NCDOT 500	500-5	1	LS		
30	Conditioning Existing Base	NCDOT 535	535-3	2000	SY		
31	Asphalt Curing Seal	NCDOT 543	543-5	195	GAL		
32	Milling Asphalt Pavement, 0.0" to 3.00"	NCDOT 607	607-5	1,300	SY		
33	Mobilization (5% of Base Bid)	NCDOT 800	800-2	1	LS		
34	Construction Surveying	NCDOT 801	801-3	1	LS		
35	Pipe Plug	NCDOT 840	840-4	0.12	CY		
38	Geotextile for Drainage - Riprap	NCDOT 876	876-4	100	SY		
39	Select Materials	NCDOT 1016	-	1,900	TN		
40	HDPE/HDPP Flared End Section, 24"	NCDOT 1032	-	1	EA		
41	Tubelings	NCDOT 1060	-	14	EA		
42	Tree Planting (1-gal container)	NCDOT 1060	-	8	EA		
43	Level A Subsurface Utility Exploration*	NCDOT 1500	1500-10	1	ALLOWANCE		15,000
44	Utility Coordination*	NCDOT 1500	1500-10	1	ALLOWANCE		15,000
45	Temporary Silt Fence	NCDOT 1605	1605-5	470	LF		
46	Seed for Temporary Seeding	NCDOT 1620	1620-4	30	LBS		
47	Fertilizer for Temporary Seeding	NCDOT 1620	1620-4	0.13	TN		
48	Standard Gravel Yard Inlet Protection	NCDOT 1632	1632-5	1	EA		
49	Standard Pipe Inlet Protection (Plywood & Stone)	NCDOT 1635	1635-5	3	EA		
50	Selective Tree Removal, 12"	NCDOT 1651	1651-5	4	EA		
51	Selective Tree Removal, 16"	NCDOT 1651	1651-5	2	EA		
52	Selective Tree Removal, 17"	NCDOT 1651	1651-5	1	EA		
53	Selective Tree Removal, 18"	NCDOT 1651	1651-5	1	EA		
54	Seeding and Mulching	NCDOT 1660	1660-8	0.25	AC		
55	Standard Filter Bag for Dewatering Activities	-	-	1	EA		

REVISED

ITEM NO.	DESCRIPTION	SPEC SECTION	PAY ITEMS PARAGRAPH	QUANTITY	UNIT	UNIT PRICE	TOTAL
56	Standard Silt Bag – Inlet Sediment Control Device	-	-	5	EA		
57	Stream Pump Around and Diversion Measures	-	-	1	LS		
58	As-Built Survey*	-	-	1	ALLOWANCE		20,000
59	Post-Construction CCTV*	-	-	1	ALLOWANCE		10,000
60	Geotechnical Services*	-	-	1	ALLOWANCE		15,000

Bid Alternate

ITEM NO.	DESCRIPTION	SPEC SECTION	PAY ITEMS PARAGRAPH	QUANTITY	UNIT	UNIT PRICE	TOTAL
61	Road Replacement	-	-	1	LS		

**Total provided by engineer to be used across all bids as an allowance/contingency at the Town's discretion.*