

Project: Harper Park Drainage and Street Improvements
Project Number: 21-607000-001

Topic: Response to Questions #2 dated 10/1/2020

Is there a fencing specification for temporary construction fencing?

The Town believes that due to the nature of the work, the short duration of the project and the ability of the contractor to block off the parking area, that standard tree protection fencing, along with appropriate signage will suffice to keep the public from the jobsite. The Town understands that this is a very small job site and mobility will be required. Contractor should bid accordingly. If during the construction sequence the Contractor see a need to change to a more permanent type of fencing, the Town can evaluate, and any such change be handled by change order.

Will the contractor be required to provide "as built" at project completion?

Yes, the Contractor will be responsible with providing the Town with an "as-builts" complete with inverts and pipe locations for all infrastructure installed. Additionally, the contractor, or surveyor should provide a GIS file layer of all installed infrastructure. The data structure for the GIS layer can be obtained from the Town's Stormwater Department.

The paving detail for alternate #1 shows 6" ABC and 3" asphalt, is this correct?

No, unfortunately the wrong paving specification was used. This should be listed as 8" compacted ABC, with two lifts of 1.5" (intermediate and finish course 3" total). A correction on this detail will be included as part of the final plan set.