

SITE VICINITY MAP NOT TO SCALE

GENERAL PROJECT DATA 1. TOTAL NUMBER OF LOTS 48 2. TOTAL ACRES 8.91 AC 3. TOTAL DISTURBED AREA 5.19 AC 4. WATER (PUBLIC WATER) 5. SEWER (PUBLIC SEWER) 6. BUILDING SETBACKS: FRONT: 0 '- 25' SIDE: 10' BETWEEN BUIDLINGS

REAR: NONE

PUBLIC IMPROVEMENT		
Mingo Creek Phase 7		
Number of Lots	48	
Lot Numbers	700-747	
Public Water Service Stubs	48	
Public Sewer Service Stubs	48	
Public Water (LF)	1,103	
Public Sewer (LF)	956	
Public Street (LF)	313	
Private Street (LF)	938	
Standard Transition to Valley Curb	100	
30" Standard Curb (LF)	581	
30" Valley Curb (LF)	1,443	
Public Sidewalk (LF)	579	
Private 5.5' Sidewalk (LF)	1,250	
Private 6' Sidewalk (LF)	228	
Public Storm Drainage (LF)	189	
Private Storm Drainage (LF)	551	
Public Greenway	0	

Public Water Distribution / Extension System ne City of Raleigh consents to the connection and extension of the City's public water system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. Public Utilities Department Permit # Authorization to Construct

Public

Sewer Collection / Extension System The City of Raleigh consents to the connection and extension of the City's public sewer system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. Public Utilities Department Permit #

Authorization to Construct

DEVELOPER/APPLICANT:

MINGO CREEK INVESTMENTS III, LLC 2102 PRITCHARD RD Clayton, NC 27527

CONTACT/AGENT: DAVE DEYOUNG 919-901-3178



CONSTRUCTION DRAWINGS

SU-2-01

MINGO CREK PHASE 7

KNIGHTDALE, WAKE COUNTY, NC Approved

SHEET INDEX

Town Approved Standards Shall Control. In the event of a conflict or inconsistency between these construction drawings and the Town of Knightdale's Approved Standards for this project, the Approved Standards shall control. Town of Knightdale Approved Standards shall mean all development documents necessary for approval for the Property including, but not limited to, any special use permit, subdivision plan, site plan, subdivision plat(s), phasing schedule, Development Agreement, Utility Allocation Agreement, Annexation Agreement, the Town of Knightdale Standard Specification and Details Manual and applicable provisions of the North Carolina State Building Code.

Professional Design Engineer Certification. These improvements shall be constructed in accordance with the following drawings and with the Standard Specifications of the Town of Knightdale.

, PE, certify that the Standard Specifications of the Town of Knightdale have been thoroughly checked and found to be applicable to this project. All exceptions to the applicable Town standards have been previously approved by the Town of Knightdale and said exceptions are shown on Sheet(s) of these drawings. Seal By:

Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of Knightdale


Town Engineer These plans are approved by the Town of Knightdale and serve as construction plans for this project.

PLAT OF THE SUBDIVISION AND 20' CORWLE MUST BE SUBMITTED TO BOTH TOWN OF KNIGHTDALE AND CORPUD FOR REVIEW PRIOR TO RECORDING. THE PLAT MUST BE RECORDED PRIOR TO THE ISSUANCE OF UTILITY BUILDING PERMITS FROM THE TOWN

Administrator

SHEET TITLE SHEET No.

EXISTING CONDITIONS	EX1
SITE PLAN	C1
UTILITY & STORM DRAINAGE PLAN	C2
GRADING & EROSION CONTROL PLAN	C3
HOWDENSHIRE RUN PLAN & PROFILE	C4
DREWTON STREET PLAN & PROFILE	C5
STORMWATER MANAGEMENT PLAN	C6
SIGNAGE & MARKING PLAN	C7
LANDSCAPE PLAN	C8
LIGHTING PLAN	C9
DETAILS - EROSION	D1-D3.02
DETAILS - WATER	D4-D7
DETAILS - SEWER	D7-D9
DETAILS - SIGNAGE & MARKING	D10
DETAILS - LANDSCAPE	D11



NOT RELEASED FOR CONSTRUCTION

Conditions to be met prior to approval of a Construction Improvements Permit:

- 1. That tree protection fencing be installed along the 50' Special Highway Overlay District as shown on the preliminary plat and that this fencing be Inspected and approved by the Planning Department prior to the issuance of a Construction Improvements Permit; and that a tree protection plan, including fence installation and Town approval, be approved for the Neuse River buffer areas to protect existing vegetation prior to the issuance of a Construction Improvements Permit;
- 2. That the sidewalk be included and shown on approved construction plans on both sides of Mingo Bluff Boulevard and the street identified as Street 1;
- 3. That the linear pattern of the townhome units along the Eastern Wake Expressway be redesigned to provide 'pods' of townhome units with a common open space more in keeping with the layouts as proposed for the rest of the proposed development;
- 4. That at least two canopy trees be shown on construction plans in front of each townhome building to better create a streetscape
- 5. That a note be added to the plans that all trashcans within the townhome units will be screened from view of the public and private streets, and that a detail be provided on construction plans on how screening is to be achieved;
- 6. That as recommended by the Parks & Recreation Advisory Board that specific recreation equipment and construction details of the recreation areas be reviewed and approved by the Parks & Recreation Advisory Board prior to issuance of a Construction Improvements Permit; that play equipment for the Tot Lots shall be IPEMA certified and include vendors such as Little Tykes, Recreation Creations and Landscape Structures; and that a bridge be provided over the stream (subject to Division of Water Quality approval) to connect the townhome pod to the sidewalk system in the southeast corner;
- 7. That a fencing system, including a split rail or similar fence (not just shrubbery) be installed between the active recreation area and Mingo Bluff Boulevard to provide a barrier to the road; and that the multi-purpose path be an asphalt at least 6 feet wide;
- 8. That the applicant be requested to voluntarily reserve an easement in the Northeast corner of the development to accommodate a future rail transit stop parking area;

Conditions to be met prior to Planning Department authorization to record lots:

- 9. That the recombination plat reflecting the 104.24 acres be approved by the Knightdale Planning Department, be recorded at the Wake County Register of Deeds and that 3 copies and 1 mylar be submitted to the town;
- 10. That homeowners documents incorporating this subdivision into the existing Mingo Creek homeowners association for all of Phase III are required to be approved by the Town Attorney and recorded at the Wake County Register of Deeds, and that a copy be submitted to the Town Planning Department within 14 days of authorization of map recording for any section of Phase III; and that the homeowners documents reflect responsibility for maintenance of recreation areas and open space;

Conditions that are to be met prior to issuance of Certificate of Occupancy:

- 11. That Mingo Bluff Boulevard be installed in its entirety prior to issuance of the first Certificate of Occupancy on any lot within the
- 12. That the portion of the Type D buffer yard along the future Eastern Wake Expressway located within Phase 12 be completely installed prior to issuance of any building permit for Phase 12; that the portion of the Type D buffer yard along the future Eastern Wake Expressway located within Phase 7 be completely installed prior to the issuance of any building permit for Phase 7; that the portion of Type D buffer yard along the future Wake County Expressway located with Section 8 be completely installed prior to the issuance of any building permit for Section 8;
- 13. That the Type A buffer yard required along the southern portion of the property line be installed prior to the issuance of the first Certificate of Occupancy for Section 8 and the Type A buffer yard along the Northern property line be installed prior to the issuance of the first Certificate of Occupancy for Section 3;
- 14. That the active recreation area on Mingo Bluff Boulevard (containing the tot lots and gazebo areas) be constructed and completed prior to the issuance of the first Certificate of Occupancy of a house in Phase III; and that all other recreation areas, including all amenities (i.e. Multi-purpose path and basketball court), be constructed prior to the issuance of a Certificate of Occupancy for any house within the specific section that the recreation area is located within;
- 15. That the homes be built as follows: The minimum size of the townhomes with garages shall be a minimum of 1,400 square feet of heated floor space and townhomes without garages shall be a minimum of 1,000 square feet of heated floor space. The detached single family homes shall be a minimum of 1,300 square feet of heated floor space as agreed upon by Mr. Fred Smith.

Approved by the Town Council, the request includes the following list of conditions and permitted uses; R-12 CUD Uses; Streets, CP&L power line easement and Open Space

Use Number 6.24, Public Park

R-10 CUD Use Number 1.11, Single Family Detached

Use Number 6.24, Public Park

Minimum Lot Size; 10,000 square feet Average Lot Size; 11,000 square feet

Total Acreage 108.9

R-7 CUD Use Number 1.11, Single Family Detached

Use Number 6.24, Public Park

Minimum Lot Size; 8,000 square feet

Average Lot Size; 9,000 square feet Total Acreage 96.3

R-MT CUD Use Number 1.11, Single Family Detached

Use Number 6.24, Public Park

Use Number 1.13, Zero Lot Line Use Number 1.21, Duplex

Use Number 1.31, Apartments

Use Number 1.32, Condominiums

Use Number 1.33, Townhouses Maximum density will not exceed ten units per acre.


Total Acreage 55.0

In the event that tracts shown as R-MT CUD develop as single family detached residential, such tracts will be permitted to



FEBRUARY 24, 2017

REVISED 06/14/2019 PER TOK COMMENTS REVISED 08/26/2021 PER COR & TOK COMMENTS REVISED 01/26/2022 PER CLIENT COMMENTS





MINGO PHAS


DRAWN
ADS/BRL
CHECKED
DCA
HORIZONTAL SCALE
SEE GRAPHIC SCALE

02/24/2017 JOB NO.

EX1







IORIZONTAL SCA SEE GRAPHIC SCALE 02/24/2017




PER CHANGE IN THE NORTH CAROLINA GERNERAL STATUTES (NCGS 87-121(g)), UNDERGROUND UTILITIES ARE TO BE LOCATED BY ELECTRONIC MEANS. SIMILAR TO OTHER DETAILS, GRAVITY SEWER MAINS NOW REQUIRE A #12 AWG INSULATED (GREEN) SOLID COPPER WIRE TO BE PLACED WITH THE GRAVITY SEWER MAIN. IF THE SEWER MAIN DEPTH IS GREATER THAN 8 FEET FROM FINAL SURFACE ELEVATION, PLACE THE WIRE AT A DEPTH BETWEEN 7 AND 8 FEET BELOW FINAL SURFACE ELEVATION. IN PAVED AREAS, PROVIDE ACCESS TO THE TRACER WIRE THROUGH A MINI-MANHOLE. IN AN OUTFALL CONDITION, PROVIDE ACCESS SIMILAR TO THE WATER LINE TRACER WIRE DETAIL. LOOP THE WIRE AROUND THE STANDARD MANHOLE. SEE DETAIL ON SHEET D2

1. ALL STORM STRUCTURES SHOWN ARE NCDOT STD. CATCH BASIN WITH THE EXCEPTIONS OF SD10 WHICH IS A NCDOT STD. DROP INLET AND SD4, SD11 AND SD11A WHICH ARE VALLEY GRATES. PLEASE SEE DETAIL ON SHEET C3 FOR STANDARD CATCH BASIN CURB TRANSITION

2. PIPE/MAIN CROSSINGS: STORMWATER OVER WATER MAIN; MIN. 18" CLEARANCE WITH ONE JOINT DIP WATERLINE CENTERED UNDER STORMDRAIN. 3. PIPE/MAIN CROSSINGS: STORMWATER OVER SANITARY SEWER MAIN; MIN. 24"

4. HORIZONTAL PIPE/MAIN SEPARATION; 10' MIN. CLEAR BETWEEN WATER/SEWER OR INSTALL WATER 18" OVER SEWER IN SEPARATE TRENCH OR USE DIP OR ENCASEMENT ON BOTH MAINS.


LEGEND			
EXISTING		PROPOSED	
— w —	WATERLINE —— 6 BLOWOFF HYDRANT	" WL —	
\bowtie	VALVE	M	
\triangleright	REDUCER	>	
0	METER	W	
ss	SEWERLINE	— ss ——	
\circ	MANHOLE	S	
0	CLEANOUT	S	
STO	ORM DRAINAGE		
□ CA	ATCH BASIN		
⊠ DROP	INLET/YARD INLET	∑	





REVISED

NOT RELEASED FOR CONSTRUCTION



(IN FEET) 1 inch =40 ft.

TOK SU-2-01

S

HOWDENSHIRE RUN PLAN & PROFILE

HORIZONTAL SCALE
SEE GRAPHIC SCALE 02/24/2017

Town Engineer These plans are approved by the Town of Knightdale and serve as construction plans for this project.

Administrator

VARIABLE WIDTH

EXTENDS TO 10FT BEYOND

THE WATER, SEWER, AND STORM

PUBLIC UTILITY EASEMENT

EL = 223.0

PERM. GRASS -REINFORCEMENT LINER

SEE EROSION PLAN

20' DRAINAGE EASEMENT

RIORETENTION BASIN

BOTTOM EL = 236.0 \

SEE DETAIL THIS SHEET

OUTLET DISSIPATOR

MANHOLE. SEE DETAIL ON SHEET D2

ENCASEMENT ON BOTH MAINS.

714

- 20 DRAINAGE EASEMENT

RISER #2

DRY DETENTION BASIN

BOTTOM EL = 236.5 SEE DETAIL THIS SHEET

> 20' PUBLIC DRAINAGE EASEMENT AROUND THE

TWO SCM'S.

1. ALL STORM STRUCTURES SHOWN ARE NCDOT STD. CATCH BASIN WITH THE EXCEPTIONS OF SD10 WHICH IS A NCDOT STD. DROP INLET AND SD11 WHICH SHALL MATCH CURB SECTION.

2. PIPE/MAIN CROSSINGS: STORMWATER OVER WATER MAIN; MIN. 18" CLEARANCE WITH ONE JOINT DIP WATERLINE CENTERED UNDER STORMDRAIN.

3. PIPE/MAIN CROSSINGS: STORMWATER OVER SANITARY SEWER MAIN; MIN. 24"

PER CHANGE IN THE NORTH CAROLINA GERNERAL STATUTES (NCGS 87-121(g)), UNDERGROUND UTILITIES ARE TO BE LOCATED BY ELECTRONIC MEANS. SIMILAR TO OTHER DETAILS, GRAVITY SEWER MAINS NOW REQUIRE A #12 AWG INSULATED

(GREEN) SOLID COPPER WIRE TO BE PLACED WITH THE GRAVITY SEWER MAIN. IF

ELEVATION, PLACE THE WIRE AT A DEPTH BETWEEN 7 AND 8 FEET BELOW FINAL SURFACE ELEVATION. IN PAVED AREAS, PROVIDE ACCESS TO THE TRACER WIRE

THROUGH A MINI-MANHOLE. IN AN OUTFALL CONDITION, PROVIDE ACCESS SIMILAR

TO THE WATER LINE TRACER WIRE DETAIL. LOOP THE WIRE AROUND THE STANDARD


THE SEWER MAIN DEPTH IS GREATER THAN 8 FEET FROM FINAL SURFACE

CLEARANCE. 4. HORIZONTAL PIPE/MAIN SEPARATION; 10' MIN. CLEAR BETWEEN WATER/SEWER OR INSTALL WATER 18" OVER SEWER IN SEPARATE TRENCH OR USE DIP OR

4—INCHES TOPSOIL (APPROX) WITH ESTABLISHED FINAL SEEDED GRASS ——COVER. USE TEMP. REINFORCEMENT LINING N.A.G. S75 OR EQUAL. (SEE PLAN FOR MORE RIGID LINING AT POND SPILLWAY & OVERFLOW SLOPE) DESIGN/ATTENUATION ELEV. 2 SEPARATE RISERS— TO SEPARATE WATER QUALITY TREATMENT VOLUME FROM OVERFLOW VOLUME TOP OF DAM ELEV. TOP OF SPILLWAY ELEV. (SEE PLAN VIEW & DETAILS BELOW) (SEE PLAN VIEW FOR SPILLWAY LINING) COMPACTED CLAY DAM CORE KEYED BELOW OUTLET PIPE - FIELD INSPECTION & SOIL/COMPACTION SPECS PER CONTRACTOR'S INDEPENDENT TESTING FIRM GRADE TO DRAIN WATER QUALITY VOLUME -STORAGE ELEV. FOR "EXTENDED" DRY POND BASE EXTENSION OR CONCRETE FOOTING PER APPROVED SHOP DRAWINGS (AS NEEDED FOR ANTI-FLOTATION) SCM #1 - EXTENDED DRY DETENTION SECTION DETAIL NO SCALE POND DATA CHART DRY POND INFO **ELEVATION** DIMENSION 1. Install all required erosion control measures prior to pond grading (ref: Erosion Control Plan) Use temporary seeding as required during grading operations. Use reinforcement matting with final seeding in accordance with this Plan and/or the Erosion Control Plan. 10' WIDTH 245.00 SPILLWAY 30' LENGTH 243.75 Pipe Outlets: See Plan View and/or Erosion Control Plan for Pipe Outlet Dissipator from Riser Structure #2. Pipe outlet from Riser Structure #1 discharges at slow velocity to SCM-2 (Bioretention) with no dissipator required. RISER STRUCTURE #1: TOP OF CONCRETE BOX RISER 4'L X 4'W 244.50 CORED ORIFICE(S) 2" PVC FITTING W/SMALL ORIFICE 1.0" SM. ORIFICE DIA. 3. Pond Overflow Spillway: See Plan View and/or Erosion Control Plan for Spillway Lining. 236.50 (AT POND BOTTOM) OUTLET PIPE(S) INVERT INLET 1-12" RCP 1-12" RCP 236.50 3. LOCATE & CONSTRUCT RISER STRUCTURES IN FIELD AS FAR AS PRACTICAL OUTET PIPE(S) INVERT OUTLET 236.00 WITHIN INSIDE SLOPE OF POND DAM FOR MAXIMUM FLOTATION RESISTANCE. RISER STRUCTURE #2:
TOP OF CONCRETE BOX RISER 4'L X 4'W 243.00 CORED ORIFICE(S) 1-6" DIAMETER 242.25 2" PVC FITTING W/SMALL ORIFICE

N/A 236.50

223.00




RISER STRUCTURE #1 NO SCALE

1-18" RCP 1-18" RCP

(AT POND BOTTOM) OUTLET PIPE INVERT INLET


OUTET PIPE(S) INVERT OUTLET

RISER STRUCTURE #2 NO SCALE






REVISED 1/26/2022 8:02 AM NOT RELEASED FOR CONSTRUCTION








TOK SU-2-01


MINGO PHAS


02/24/2017

HORIZONTAL SCALE SEE GRAPHIC SCALE




DRAWN
ADS/BRL
CHECKED
DCA
HORIZONTAL SCALE
SEE GRAPHIC SCALE DATE 02/24/2017 JOB NO.





COUNTY NORTH CAROLINA

EFFECTIVE: 01/31/0



STANDARD SILT FENCE OUTLET

<u>Section view</u>

BURY WIRE FENCE, FILTER FABRIC, AND HARDWARE CLOTH IN TRENCH



1. SCHEDULE A SITE MEETING WITH THE ENVIRONMENTAL ENGINEER/CONSULTANT TO DETERMINE IF BASIN CAN BE REMOVED. INSTALL SILT FENCING OR OTHER TEMPORARY EROSION CONTROL MEASURES AS NEEDED PRIOR TO REMOVAL OF THE BASIN. 2. REMOVE BASIN(S) AND ASSOCIATED TEMPORARY DIVERSION DITCHES. IF THE CULVERT PIPES NEED TO BE EXTENDED, PERFORM THIS OPERATION AT THIS TIME. FINE GRADE AREA IN PREPARATION FOR SEEDING. 3. PERFORM SEEDBED PREPARATION, SEED, MULCH AND ASPHALT TACK ANY RESULTING BARE AREAS IMMEDIATELY. 4. INSTALL VELOCITY DISSIPATORS AND/OR LEVEL SPREADERS AS REQUIRED ON THE EROSION CONTROL PLAN. 5. WHEN SITE IS FULLY ESTABLISHED, CALL ENVIRONMENTAL ENGINEER/CONSULTANT FOR APPROVAL OF REMOVING REMAINING TEMPORARY EROSION CONTROL MEASURES AND

ADVICE ON WHEN SITE CAN BE ISSUED A CERTIFICATE OF COMPLETION.


Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of Knightdale.


These plans are approved by the Town of Knightdale and serve as construction plans for this project.


NOT RELEASED FOR CONSTRUCTION


TOK SU-2-01


REVISED




















S MINGO PHAS


HORIZONTAL SCALE SEE GRAPHIC SCALE 02/24/2017














DEPTH OF SCOUR HOLE (1' MIN. - 3' MAX.)


W/ TYPE 2 FILTER FABRIC
DEPTH OF RIPRAP (1')


SQUARE PREFORMED SCOUR HOLE (PFSH) (RIPRAP IN BASIN NOT SHOWN FOR CLARITY)

Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of Town Engineer

Knightdale. These plans are approved by the Town of Knightdale and serve as construction plans for this project.









NOT RELEASED FOR CONSTRUCTION

TOK SU-2-01

02/24/2017

MINGO CREEK PHASE 7

DETAILS - EROSION (WAKE COUNTY STD)

DESIGN *DCA*

DRAWN *ADS/BRL*

CHECKED

DCA


HORIZONTAL SCALE

SEE GRAPHIC SCALE


VERTICAL SCALE
N/A


STANDARD GRAVEL BAG CURB INLET PROTECTION

EFFECTIVE: 01/31




STANDARD SILT BAG - INLET SEDIMENT CONTROL DEVICE





UDO NOTE ADDED AND RENUMBERED "001" 11-1-2013, WDP



SEEDBED PREPARATION

1. CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE.

2. RIP THE ENTIRE AREA TO 6 INCH DEPTH.

3. REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY SMOOTH AND UNIFORM.

4. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL (SEE BELOW).

5. CONTINUE TILLAGE UNTIL A WELL-PULVERIZÉD, FIRM, REASONABLY

UNIFORM SEEDBED IS PREPARED 4 TO 6 INCHES DEEP. 6. SEED (150 IBS/ACRE) ON A FRESHLY PREPARED SEEDBED AND COVER

SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING. 7. MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH. 8. INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR

RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND IS OVER 60% DAMAGED, RE-ESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.

9. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.

PREPARATION

* AGRICULTURAL LIMESTONE - 2 TONS/ACRE (3 TONS IN CLAY SOIL)

* FERTILIZER - 1,000 LBS/ACRE - 10/10/10

* SUPERPHOSPHATE - 500 LBS/ACRE - 20% ANALYSIS * MULCH - 2 TONS/ACRE - SMALL GRAIN STRAW

* ANCHOR - ASPHALT EMULSION @ 300 GALS/ACRE

1. TEMPORARY SEEDING

* SEE TABLES BELOW: 2. PERMANENT SEEDING

* TALL FESCUE,

100 LB/ACRE * SERICEA LESPEDEZA, 15 LB/ACRE

Table 6.10a | Seeding mixture Temporary Seeding Rate (lb/acre) Recommendations for Late Winter and Early Spring Annual lespedeza (Kobe in Piedmont and Coastal Plain, Korean in Mountains) Omit annual lespedeza when duration of temporary cover is not to extend beyond June. Seeding dates Mountains-Above 2500 feet: Feb. 15 - May 15 Below 2500 feet: Feb. 1- May 1 Piedmont—Jan. 1 - May 1 Coastal Plain—Dec. 1 - Apr. 15 Soil amendments Follow recommendations of soil tests or apply 2,000 lb/acre ground agricultural limestone and 750 lb/acre 10-10-10 fertilizer. Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch anchoring tool. A disk with blades set nearly straight can be used as a mulch anchoring tool.

Table 6.10b	Seeding mixture		
Temporary Seeding	Species	Rate (lb/acre)	
Recommendations for Summer	German millet	40	
	In the Piedmont and Mountains, a small-stemmed Sudangrass may be substituted at a rate of 50 lb/acre.		
	Seeding dates		
	Mountains—May 15 - Aug. 15		
	Piedmont—May 1 - Aug. 15		
	Coastal Plain—Apr. 15 - Aug. 15		
	Soil amendments		
	Follow recommendations of so	il tests or apply 2,000 lb/acre ground	

ests or apply 2,000 lb/acre ground agricultural limestone and 750 lb/acre 10-10-10 fertilizer.

Refertilize if growth is not fully adequate. Reseed, refertilize and mulch

immediately following erosion or other damage.

Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch anchoring tool. A disk with blades set nearly straight can be used as a mulch anchoring tool.

Refertilize if growth is not fully adequate. Reseed, refertilize and mulch immediately following erosion or other damage.

Table 6.10c Seeding mixture Temporary Seeding Species Recommendations for Fall Rye (grain)

REVISED

NOT RELEASED FOR

CONSTRUCTION

Rate (lb/acre)

Mountains—Aug. 15 - Dec. 15 Coastal Plain and Piedmont—Aug. 15 - Dec. 30

Soil amendments Follow soil tests or apply 2,000 lb/acre ground agricultural limestone and 1,000 lb/acre 10-10-10 fertilizer.

Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch anchoring tool. A disk with blades set nearly straight can be used as a mulch anchoring tool.

Maintenance Repair and refertilize damaged areas immediately. Topdress with 50 lb/acre of nitrogen in March. If it is necessary to extent temporary cover beyond June 15, overseed with 50 lb/acre Kobe (Piedmont and Coastal Plain) or Korean (Mountains) lespedeza in late February or

Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of Knightdale.

> Town Engineer These plans are approved by the Town of Knightdale and serve as

construction plans for this project. Administrator

TOK SU-2-01

S MINGO

DETAILS - EROSION (WAKE COUNTY STD)

ADS/BRL HORIZONTAL SCALE SEE GRAPHIC SCALE

02/24/2017

HORIZONTAL SCAL

02/24/2017

D3.01

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes			
Site Area Description		Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b)	High Quality Water (HQW) Zones	7	None
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
 Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Rolled erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	 Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- 4. Provide ponding area for containment of treated Stormwater before discharging
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- 1. Maintain vehicles and equipment to prevent discharge of fluids.
- 2. Provide drip pans under any stored equipment.
- 3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- 4. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- 5. Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- 1. Never bury or burn waste. Place litter and debris in approved waste containers.
- 2. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- 3. Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- 4. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- 5. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- 6. Anchor all lightweight items in waste containers during times of high winds.
- 7. Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE

- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- 2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.


PORTABLE TOILETS

- . Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- 1. Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.





CONCRETE WASHOUTS

- 1. Do not discharge concrete or cement slurry from the site.
- 2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- 8. Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

- 1. Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning
- 3. Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site
- 2. Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.

EFFECTIVE: 04/01/19

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

HORIZONTAL SCAL

02/24/2017

D3.02

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend of holiday periods, and no individual-day rainfall information available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection needed). Days on which no rainfall occurred shall be recorded a "zero." The permittee may use another rain-monitoring devices.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 approved by the Division. Identification of the measures inspected, Date and time of the inspection, Name of the person performing the inspection, Indication of whether the measures were operating properly, Description of maintenance needs for the measure, Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 Identification of the discharge outfalls inspected, Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, Indication of visible sediment leaving the site, Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 If visible sedimentation is found outside site limits, then a record of the following shall be made: Actions taken to clean up or stabilize the sediment that has lef the site limits, Description, evidence, and date of corrective actions taken, an An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit of this permit.
(6) Ground stabilization measures	After each phase of grading	 The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be documented in the manner described:

Item to Document	Documentation Requirements
(a) Each E&SC Measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC Plan.	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
c) Ground cover is located and installed naccordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
d) The maintenance and repair equirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation

In addition to the E&SC Plan documents above, the following items shall be kept on the ite

and available for agency inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- (a) This general permit as well as the certificate of coverage, after it is received.
- (b) Records of inspections made during the previous 30 days. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.
- All data used to complete the Notice of Intent and older inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that must be reported

Permittees shall report the following occurrences:


- (a) Visible sediment deposition in a stream or wetland.
- (b) Oil spills if:
 - They are 25 gallons or more,
 - They are less than 25 gallons but cannot be cleaned up within 24 hours,
 - They cause sheen on surface waters (regardless of volume), or
 - They are within 100 feet of surface waters (regardless of volume).
- (a) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- (b) Anticipated bypasses and unanticipated bypasses.
- (c) Noncompliance with the conditions of this permit that may endanger health or the environment.


2. Reporting Timeframes and Other Requirements


After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Division's Emergency Response personnel at (800) 662-7956, (800) 858-0368 or (919) 733-3300.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment	Within 24 hours, an oral or electronic notification.
deposition in a	 Within 7 calendar days, a report that contains a description of the
stream or wetland	sediment and actions taken to address the cause of the deposition.
	Division staff may waive the requirement for a written report on a case-by-case basis.
	 If the stream is named on the NC 303(d) list as impaired for sediment-
	related causes, the permittee may be required to perform additional
	monitoring, inspections or apply more stringent practices if staff
	determine that additional requirements are needed to assure compliance
	with the federal or state impaired-waters conditions.
(b) Oil spills and	Within 24 hours, an oral or electronic notification. The notification
release of	shall include information about the date, time, nature, volume and
hazardous	location of the spill or release.
substances per Item	•
1(b)-(c) above	
(c) Anticipated	A report at least ten days before the date of the bypass, if possible.
bypasses [40 CFR	The report shall include an evaluation of the anticipated quality and
122.41(m)(3)]	effect of the bypass.
(d) Unanticipated	Within 24 hours, an oral or electronic notification.
bypasses [40 CFR	Within 7 calendar days, a report that includes an evaluation of the
122.41(m)(3)]	quality and effect of the bypass.
(e) Noncompliance	Within 24 hours, an oral or electronic notification.
with the conditions	Within 7 calendar days, a report that contains a description of the
of this permit that	noncompliance, and its causes; the period of noncompliance,
may endanger	including exact dates and times, and if the noncompliance has not
health or the	been corrected, the anticipated time noncompliance is expected to
environment[40	continue; and steps taken or planned to reduce, eliminate, and
CFR 122.41(I)(7)]	prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6).
	Division staff may waive the requirement for a written report on a
	case-by-case basis.









Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of Knightdale.

By:

Date:

By: ____ Date: ___ Town Engineer

These plans are approved by the Town of Knightdale and serve as construction plans for this project.

By: _____ Date: ____

Public

Water Distribution / Extension System


The City of Raleigh consents to the connection and extension of the City's public water system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.

City of Raleigh
Public Utilities Department Permit #

Authorization to Construct



NOT RELEASED FOR CONSTRUCTION



NOTES:

1. ALL PUBLIC FIRE HYDRANTS IN THE CITY OF RALEIGH AND THE MERGER TOWNS OF GARNER, ROLESVILLE, WAKE FOREST, KNIGHTDALE, WENDELL AND ZEBULON SHALL BE PAINTED CHROME YELLOW WITH HIGH REFLECTIVE ALUMINUM SILVER CAPS, BONNETS AND OPERATING NUTS.

2. ALL PRIVATE FIRE HYDRANTS SHALL BE RED.

DEPARTMENT OF PUBLIC UTILITIES

RALEIGH, GARNER, KNIGHTDALE, ROLESVILLE, WAKE FOREST, WENDELL & ZEBULON


STANDARD FIRE HYDRANT WITH


5" STORZ PUMPER NOZZLE


DWG. REVISIONS DATE REVISIONS DATE

NO. MAB 6-30-16

CITY OF RALEIGH







TOK SU-2-01

EAST MAIN STREET

LAYTON, NC 27520

2.2021-08-2

3.2022-01-2

919-243-1332

FIRM # C-4187

CLAYTON, Ne info@adamsand 919-243-1 FIRM # C-

MS & HODC

S.H.

MINGO CREEK
PHASE 7

ETAILS - WATER (C.O.R. STD)

DESIGN
DCA

DRAWN
ADS/BRL


CHECKED
DCA


HORIZONTAL SCALE
SEE GRAPHIC SCALE


VERTICAL SCALE
N/A


DATE
02/24/2017
JOB NO.


SHEET





















CONSTRUCTION

Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of



REVISED 1/26/2022 8:22 AM NOT RELEASED FOR

MINGO CREEK
PHASE 7

DETAILS - (C.O.R.

HORIZONTAL SCALE SEE GRAPHIC SCALE VERTICAL SCALE *N/A* 02/24/2017


MINGO CREEK
PHASE 7


DETAILS - WATER (C.O.R. STD)


DRAWN
ADS/BRL
CHECKED
DCA
HORIZONTAL SCALE
SEE GRAPHIC SCALE

DATE 02/24/2017 JOB NO.

TOK SU-2-01








NO.
1. DRILL
2. DOI
3. A R.
POSITI
4. BOT
WITH T
5. INST
MAIN.
6. 3/4"
7. END

CITY OF RALEIGH DEPARTMENT OF PUBLIC UTILITIES


PERMANENT WATER MAIN BLOW OFF ASSEMBLY





Town	Certification. This design has been reviewed by the Engineer for the of Knightdale, and to the best of my knowledge and belief, it conforms
o ine Knight	requirements established in the Standard Specifications of the Town cadale.
_	Date:
	Engineer
These	plans are approved by the Town of Knightdale and serve as
	uction plans for this project.
Зу:	Date:
Admii	nistrator
	Public
	Water Distribution / Extension System The City of Raleigh consents to the connection and extension of the City's public water system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook.
	City of Raleigh Public Utilities Department Permit #
	Authorization to Construct


CITY OF RALEIGH


DEPARTMENT OF PUBLIC UTILITIES












These plans are approved by the Town of Knightdale and serve as construction plans for this project.





THE TRACER WIRE SHALL BE CONTINUOUS TO THE GREATEST EXTENT POSSIBLE. FOR GRAVITY MAIN AND OR LATERAL INSTALLATIONS LESS THAN 8 FT, THE TRACING WIRE SHALL BE ATTACHED TO THE PIPE. TRACER WIRE SHALL BE LAID FLAT AND SECURELY AFFIXED TO THE PIPE AT 10 FOOT INTERVALS. FOR GRAVITY MAIN AND OR LATERAL INSTALLATION DEEPER THAN 8 FT, THE TRACING WIRE SHALL BE INSTALLED AT A DEPTH OF 7-8 FT. THE WIRE SHALL BE PROTECTED FROM DAMAGE DURING THE EXECUTION OF THE WORK. NO BREAKS OF CUTS IN THE TRACER WIRE SHALL BE PERMITTED. WHERE LATERAL TAPS ARE MADE BY SERVICE SADDLES, THE TRACER WIRE SHALL NOT BE ALLOWED


TO TO BE PLACED BETWEEN THE SADDLE AND MAIN. MANHOLE MARKERS SHALL BE PLACED ADJACENT TO MANHOLES AT THE DISCRETION OF OWNER OR OWNER'S REPRESENTATIVE.


DEPARTMENT OF PUBLIC UTILITIES				
	•		MAIN TRACER WIRE OLE MARKER	
DWG. NO.	REVISIONS	DATE	REVISIONS	DATE
S-20A	WKD	09-14		
J-20A				

CITY OF RALEIGH












NOT RELEASED FOR CONSTRUCTION **TOK SU-2-0**


S MINGO PHAS


> S R ETAIL!


HORIZONTAL SCALE
SEE GRAPHIC SCALE ERTICAL SCALE
N/A


02/24/2017















These plans are approved by the Town of Knightdale and serve as construction plans for this project. Administrator **Public** Water Distribution / Extension System The City of Raleigh consents to the connection and extension of the City's public water system as shown on this plan. The material and Construction methods used for this project shall conform to the standards and specifications of the City's Public Utilities Handbook. City of Raleigh Public Utilities Department Permit #


Town Engineer


Authorization to Construct

Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of

CONSTRUCTION










TOK SU-2-01


MINGO CREEK PHASE 7


HORIZONTAL SCALE 02/24/2017 JOB NO.
























Public Utilities Department Permit # Authorization to Construct _____

MINGO CREEK PHASE 7

SEWER STD) DETAILS - (C.O.R.


HORIZONTAL SCALE SEE GRAPHIC SCALE 02/24/2017

MINGO CREEK PHASE 7

TAILS - SIGNAGE & MARKINGS DE DESIGN DCA ADS/BRL CHECKED *DCA* HORIZONTAL SCALE
SEE GRAPHIC SCALE VERTICAL SCALE

N/A

02/24/2017 JOB NO.



CURB & GUTTER

STD. NO.

4.04

PROPOSED 4° CONCRETE SIDEWALK

DETAILS SHOWING EXPANSION JOINTS

IN CONCRETE SIDEWALK

A GROOVE JOINT 1" DEEP WITH 1/8" RADII SHALL BE

2. SIDEWALK AT DRIVEWAY ENTRANCES TO BE 6" THICK.

3. WIDTH OF SIDEWALK ON THOROUGHFARE STREETS SHALL BE A MINIMUM OF 5', WIDTH OF SIDEWALKS IN THE CENTRAL BUSINESS DISTRICT WILL BE DETERMINED BY THE TOWN ENGINEER

4. WIDTH OF SIDEWALKS ON NON-THOROUGHFARE STREETS SHALL BE A MINIMUM OF 5' UNLESS OTHERMSE

SPECIFIED BY THE TOWN'S UNIFIED DEVELOPMENT

CONCRETE COMPRESSIVE STRENGTH SHALL BE 3600 PS IN 28 DAYS.

SIDEWALK TO BE POURED TO END OF RADIUS AT INTERSECTING STREETS.

CONCRETE SIDEWALKS

REQUIRED IN THE CONCRETE SIDEWALK AT 5' INTERVALS

INTERVALS NOT TO EXCEED 50' AND MATCHING EXPANSION/CONSTRUCTION JOINT IN ADJACENT CURB. A SEALED 1/2" EXPANSION JOINT WILL BE REQUIRED WHERE THE SIDEWALK JOINS ANY RIGID STRUCTURE.

-1/8° TO 1/4"

GROOVE JOINT IN SIDEWALK

1/2"---

TRANSVERSE EXPANSION

JOINT IN SIDEWALK


1/8" RADIUS -


REVISIONS


TOWN OF KNIGHTDALE


STANDARD DETAILS


DESCRIPTION

























CONSTRUCTION

Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of Knightdale. Town Engineer These plans are approved by the Town of Knightdale and serve as

construction plans for this project.

Administrator

SCOPE OF WORK: FURNISH ALL LABOR, MATERIALS, AND EQUIPMENT REQUIRED OR INDICATED BY THE DRAWINGS AND SPECIFICATIONS TO COMPLETE THE WORK OF THIS SECTION INCLUDING INSTALLATION OF TREES, SHRUBS, GROUND COVERS, PERENNIALS, SOD, SEEDING, MULCH, AND APPURTENANCES.

JOB CONDITIONS: ATTENTION SHALL BE DIRECTED TO THE LOCATION OF ACTIVE UTILITIES WITHIN THE LIMITS OF WORK. BEFORE COMMENCING ANY WORK REQUIRED BY THE CONTRACT, THE CONTRACTOR SHALL LOCATE ALL UTILITIES, SUBSURFACE DRAINAGE, AND UNDERGROUND CONSTRUCTION SO THAT PROPER PRECAUTIONS MAY BE TAKEN NOT TO DISTURB OR DAMAGE ANY SUBSURFACE IMPROVEMENTS. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR MAKING, AT HIS OWN EXPENSE, ALL REPAIRS TO DAMAGED UTILITIES RESULTING FROM THE WORK COVERED BY THE CONTRACT.

MATERIALS AND WORK: THE SELECTION OF ALL MATERIALS AND THE EXECU-TION OF ALL WORK REQUIRED UNDER THE CONTRACT SHALL BE SUBJECT TO APPROVAL BY THE OWNER OR HIS AGENT. THE OWNER SHALL HAVE THE RIGHT TO REJECT ANY AND ALL MATERIALS AND ANY AND ALL WORK WHICH, IN HIS OPINION, DOES NOT MEET THE REQUIREMENTS OF THE CONTRACT DOCUMENTS AT ANY STAGE OF THE OPERATIONS. ALL REJECTED MATERIALS SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR.

PLANT MATERIALS: ALL MATERIALS SHALL BE NURSERY GROWN, FRESHLY DUG IF FIELD GROWN, NATURALLY SHAPED, AND WELL-BRANCHED; FULL FOLIAGED WHEN IN LEAF WITH HEALTHY, WELL-DEVELOPED ROOT SYSTEMS. TREES MUST BE SELF-SUPPORTING, WITH STRAIGHT TRUNKS AND LEADERS INTACT. ALL PLANTS FURNISHED SHALL BE FREE OF ANY INSECT INFESTATIONS OR THEIR EGGS, AND SHALL HAVE BEEN GROWN UNDER CLIMATIC CONDITIONS SIMILAR TO THOSE OF THE PROJECT LOCALE. ALL PLANTS SHALL BE TRUE TO SPECIES AND VARIETY.

PLANT SIZE: SPECIFIED SIZES INDICATE MINIMUM ALLOWABLE SIZES AT PLANT-ING. WHERE CONTAINER AND SIZE ARE INDICATED FOR A SINGLE SPECIES, BOTH REQUIREMENTS MUST BE MET.

PLANT HANDLING & STORAGE: PLANTS AND THEIR ROOT SYSTEMS SHALL BE ADEQUATELY PROTECTED FROM DRYING OUT AT ALL TIMES. PLANT MATERIALS SHALL BE WATERED PRIOR TO TRANSPORT AND KEPT MOIST PRIOR TO PLANTING. PLANTS THAT CANNOT BE PLANTED IMMEDIATELY UPON DELIVERY SHALL BE KEPT IN THE SHADE AND WELL-WATERED. PLANTS SHALL NOT REMAIN UNPLANTED FOR LONGER THAN THREE DAYS AFTER DELIVERY.

BALLED & BURLAPPED PLANTS SHALL BE LIFTED FROM THE BOTTOM ONLY, NOT BY STEMS OR TRUNKS.

CARE SHALL BE TAKEN WHEN REMOVING THE CONTAINER FROM CONTAINER-GROWN PLANTS SO AS NOT TO INJURE THE PLANT'S ROOTS.

SUBSTITUTIONS: IF PROOF IS SUBMITTED THAT ANY PLANT SPECIFIED IS NOT AVAILABLE, A WRITTEN PROPOSAL FOR USE OF A SIMILARLY-SIZED AND TYPE OF PLANT AND CORRESPONDING COST ADJUSTMENT WILL BE CONSIDERED. ALL SUBSTITUTIONS MUST BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.

BACKFILL MATERIAL: NATIVE SOIL SHALL NOT BE USED FOR BACKFILL BUT IS ACCEPTABLE FOR CONSTRUCTION OF REQUIRED SAUCERS AROUND PLANTS. THE REMAINDER OF UNUSED NATIVE SOIL SHALL BE HAULED AWAY FROM THE SITE. BACKFILL MATERIAL SHALL BE A BLENDED SOIL MATERIAL AND SHALL BE CONSIST OF 40% COMPOST, 35% SAND, AND 25% CLAY. THE COMPOST SHALL A TURKEY COMPOST BEARING THE U.S. COUNCIL SEAL OF ASSURANCE. THE SAND SHALL BE OBTAINED FROM A SAND QUARRY AND FREE OF ALL VIABLE WEED SEED. OTHER CONDITIONS OF THE BACKFILL SHALL BE AS FOLLOWS:

MAXIMUM SOLUBLE SALTS: 350 PPM RELATIVE DENSITY: 25%-50%, LOOSE RELATIVE PERMEABILITY: 2.5-10 IN./HR. PLASTIC INDEX: PH RANGE: 6.0-6.8

BACKFILL MATERIAL SHALL BE TESTED AND TEST RESULTS SHALL BE FURNISHED O THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO USE.

PLANT FERTILIZER: SHALL BE A COMPLETE FERTILIZER. OF WHICH 50% OF THE NITROGEN IS DERIVED FROM NATURAL ORGANIC SOURCES OR UREAFORM. IT PHOSPHORIC ACID, AND 10% POTASH. IT SHALL BE DELIVERED IN UNOPENED, LABELED CONTAINERS AND STORED IN A WEATHERPROOF PLACE.

WATER: SHALL BE FURNISHED BY THE OWNER.

PLANT MATERIAL INSTALLATION: MATERIALS SHALL ONLY BE PLANTED DURING PERIODS OF SUITABLE WEATHER CONDITIONS.

THE OWNER SHALL BE NOTIFIED OF SUBSURFACE CONDITIONS THAT WOULD PROVE DETRIMENTAL TO PLANT SURVIVAL OR GROWTH. ALTERNATE LOCATIONS FOR MATERIAL SHALL BE DETERMINED BY THE CONTRACTOR AND LANDSCAPE ARCHITECT.

ALL TREES AND SHRUBS SHALL BE PLANTED IN INDIVIDUAL HOLES. THE SIDES AND BOTTOM OF HOLES SHALL BE SCARIFIED PRIOR TO PLANTING. BACKFILL WITH THE SOIL MIXTURE SPECIFIED ON THE DRAWINGS. BACKFILLING SHALL BE ACCOMPLISHED IN LIFTS TO ENSURE ELIMINATION OF ALL AIR POCKETS. ALL PLANTS SHALL BE POSITIONED TO PLACE MOST ATTRACTIVE SIDE TO VIEW AND IN A PLUMB POSITION.

INSTALL 6 FT. DIAMETER SAUCERS MADE OF SOIL AROUND LARGE TREES AND 4 FT. DIAMETER SAUCERS AROUND SMALL TREES.

IMMEDIATELY FOLLOWING PLANTING, PLANTS SHALL BE MULCHED. WHERE PLANTS ARE PLANTED IN GROUPS, THE AREA ABOUT THE PLANT AS WELL AS THE AREA BETWEEN PLANTS SHALL BE COVERED WITH MULCH. PLANTS SHALL BE THOROUGHLY WATERED FOLLOWING MULCHING

STAKE ALL TREES IN ACCORDANCE WITH THE DRAWINGS.

PRUNING SHALL BE LIMITED TO THE REMOVAL OF INJURED BRANCHES AND TWIGS. USE CLEAN AND SHARP PRUNING TOOLS.

SIDEWALKS AND PAVEMENTS SHALL BE KEPT CLEAN DURING PROGRESS OF INSTALLATION WORK.

PLANTING BEHIND SEGMENTAL RETAINING WALLS: CONTRACTOR SHALL EXERCISE EXTREME CARE IN THE INSTALLATION OF PROPOSED TREES AND SHRUBS BEHIND SEGMENTAL RETAINING WALLS. CONTRACTOR SHALL PROCEED WITH CAUTION WHEN EXCAVATING SO AS NOT TO TEAR OR REMOVE SECTIONS OF THE GEOGRID FABRIC THAT IS TYPICALLY LOCATED 18 TO 24 INCHES BELOW FINISHED GRADE. PENETRATION OF THE GEOGRID IS PERMITTED TO PLANT INDIVIDUAL TREES OR LARGE SHRUBS AS NECESSARY: HOWEVER, EXCAVATION OF THE PLANTING HOLE AND PERFORATION OF THE GEOGRID FABRIC SHALL BE ACCOMPLISHED USING AN AUGER OR BY HAND-CUTTING THE FABRIC FOLLOWING EXCAVATION BY A BACKHOE WITH A SMOOTH-EDGE BUCKET.

MAINTENANCE OF PLANT MATERIALS: PLANT MATERIALS SHALL BE MAINTAINED FOLLOWING PLANTING AND UNTIL FINAL ACCEPTANCE IS GRANTED BY THE OWNER. MAINTENANCE SHALL CONSIST OF WATERING, WEEDING, PRUNING, MULCHING, ADJUSTMENT OF GUYING, RESTORATION OF PLANT POSITION OR SAUCERS, AND SPRAYING IF NECESSARY. FINAL ACCEPTANCE FOR SEGMENTS OF THE CONTRACT WORK MAY BE GRANTED BY THE OWNER.

THE CONTRACTOR SHALL PROTECT PLANTED AREAS WITH STAKES AND FLAGGING TO LIMIT DAMAGE.

SIDEWALKS AND PAVEMENTS SHALL BE KEPT CLEAN WHEN MAINTENANCE OPERATIONS ARE IN PROGRESS.

ALL INSTALLED MATERIALS SHALL BE IN ACCEPTABLE CONDITION WHEN CONTRACTOR APPLIES FOR PAYMENT.

NSPECTION AND ACCEPTANCE OF WORK: UPON 48 HOURS ADVANCE NOTICE, THE LANDSCAPE ARCHITECT SHALL INSPECT ALL WORK FOR ACCEPTANCE. THE CONTRACTOR'S RESPONSIBILITY FOR MAINTENANCE SHALL TERMINATE AT THE DATE OF ACCEPTANCE OF EACH SEGMENT OF WORK. UPON THE DATE OF ACCEPTANCE, THE GUARANTEE PERIOD SHALL COMMENCE.

GUARANTEE: THE CONTRACTOR SHALL GUARANTEE TO PROVIDE TO THE OWNER THRIVING PLANT MATERIALS TO INCLUDE TREES, SHRUBS, AND GROUND COVERS FOR A PERIOD OF ONE YEAR FOLLOWING FINAL ACCEPTANCE. ADDITIONALLY, THE CONTRACTOR SHALL GUARANTEE TO THE OWNER THRIVING PERENNIALS. ANNUALS. WELL-ESTABLISHED SEEDED AREAS, AND WELL-ROOTED SODDED AREAS FOR A PERIOD OF 90 DAYS FOLLOWING FINAL ACCEPTANCE. THE **GUARANTEES ARE SUBJECT TO THE FOLLOWING CONDITIONS:**

> THE OWNER IS RESPONSIBLE FOR PROPER WATERING OF PLANT MATERIALS, SEEDED AREAS, AND SODDED AREAS FOLLOWING FINAL ACCEPTANCE. THE CONTRACTOR SHALL PROVIDE TO THE OWNER WRITTEN INSTRUCTIONS SPECIFYING THE RATES AND EXTENT OF WATERING REQUIRED. THE CONTRACTOR SHALL MAKE MONTHLY INSPECTIONS FOR A PERIOD. OF (1) YEAR AT NO EXTRA COST TO THE OWNER, TO DETERMINE WHAT CHANGES, IF ANY, SHOULD BE MADE TO THE WATERING PROGRAM. ANY RECOMMENDATIONS SHALL BE SUBMITTED TO THE OWNER IN WRITING.

DAMAGE CAUSED TO PLANT MATERIALS FROM ACTS OF NATURE, VANDALISM, EROSION, OR MALICIOUS ACTS WILL VOID THE GUARANTEE FOR ANY EFFECTED MATERIALS.

DAMAGE TO PLANT MATERIALS CAUSED BY DISEASE INCLUDING BROWN PATCH IN TURF GRASSES EXCLUDE ANY EFFECTED MATERIALS FROM

PLANT MATERIAL REPLACEMENT: THE CONTRACTOR SHALL REPLACE WITHOUT COST TO THE OWNER, AND AS SOON AS WEATHER CONDITIONS PERMIT, ALL PLANTS NOT IN THRIVING CONDITION AS DETERMINED BY THE OWNER DURING AND AT THE END OF THE GUARANTEE PERIOD. THE GUARANTEE OF ALL REPLACED PLANTS SHALL EXTEND FOR AN ADDITIONAL 30 CALENDAR DAYS.

RF MATERIALS: MATERIALS REQUIRED FOR SEEDING AND OR SODDING SHALL CONFORM TO THE FOLLOWING:

FERTILIZER: SHALL BE A TURFGRADE, HIGH PHOSPHORUS FERTILIZER, IN WHICH 1/2 TO 3/4 OF THE NITROGEN IS SLOWLY AVAILABLE. IT SHALL CONTAIN BY PERCENTAGE THE FOLLOWING: 18% NITROGEN, 24% PHOS-PHORIC ACID, AND 10% POTASH. IT SHALL BE DELIVERED IN UNOPENED, LABELED CONTAINERS AND STORED IN A WEATHERPROOF PLACE.

LIME: SHALL BE NATURAL DOLOMITIC LIMESTONE CONTAINING NOT LESS THAN 85% OF TOTAL CARBONATES WITH A MINIMUM OF 30% MAGNESIUM CARBONATES IN A PELLETIZED FORM.

ANTI-EROSION MULCH: SHALL BE CLEAN, SEED-FREE SALT HAY OR THRESHED STRAW OF WHEAT, RYE, OATS, OR BARLEY.

GRASS SEED: SHALL BE FRESH, CLEAN, NEW-CROP SEED COMPLYING WITH TOLERANCE FOR PURITY AND GERMINATION ESTABLISHED BY "OFFICIAL SEED ANALYSTS OF NORTH AMERICA". PROVIDE TYPE OR MIXTURE COMPOSED OF SPECIES AS SPECIFIED ON THE CONSTRUCTION DRAWINGS.

SOD: SHALL BE FRESHLY CUT, DROUGHT-RESISTANT SOD, FREE OF OBJECTIONABLE BROADLEAF OR GRASSY WEEDS. PROVIDE TYPE AS SPECIFIED BELOW.

PREPARATION OF TURF AREAS: PRIOR TO SEEDING OR SOD INSTALLATION, VERIFY THAT ALL TRENCHING AND OTHER LAND DISTURBING ACTIVITIES HAVE BEEN COMPLETED.

ALL DISTURBED AREAS SHALL BE DRESSED TO TYPICAL SECTIONS AND GRADES SHOWN ON THE CONSTRUCTION DRAWINGS. REMOVE FROM THE SITE ALL TEMPORARY SEEDING OR STABILIZATION MEASURES.

ALL AREAS TO RECEIVE SEED OR SOD SHALL BE PREPARED ACCORDING TO THE FOLLOWING PROCEDURE:

REMOVE ANY UNDESIRABLE VEGETATION OR DEBRIS.

APPLY LIMESTONE ACCORDING TO SOIL TEST RECOMMENDATION OR AT A RATE OF 4000 LBS. PER ACRE.

RIP THE AREA TO A MINIMUM DEPTH OF 4 TO 6 INCHES.

REMOVE ALL LOOSE ROCKS, ROOTS, AND OTHER DEBRIS AND PULVERIZE THE TOP 2 INCHES OF LOOSENED SOIL TO PROVIDE A SMOOTH AND UNIFORM SURFACE.

APPLY TURFGRADE FERTILIZER IN A MANNER THAT ENSURES UNIFORM DISTRIBUTION. FERTILIZER SHALL BE APPLIED AT A RATE THAT PROVIDES 5 LBS. OF PHOSPHORUS PER 1000 S.F. LIGHTLY MIX WITH SOIL AND SMOOTH SURFACE.

SODDING: APPLY DROUGHT-RESISTANT, TURF-TYPE FESCUE SOD (E.G. "REBEL III", "BONANZA", "CONFEDERATE", ETC.) IN THE FOLLOWING MANNER

SOD SHALL BE PLACED ON A SMOOTH, EVEN SURFACE CONFORMING TO FINISH GRADE REQUIREMENTS. FINISH GRADE SHALL BE 1 INCH BELOW SURFACES OF ADJACENT SIDEWALKS AND CURBING. SOIL SHALL BE WATERED BEFORE SOD IS LAID. ALL SOD SHALL BE CUT BY AN APPROVED MECHANICAL SOD CUTTER. UNDER NO CIRCUMSTANCES SHALL ANY SODDING WORK BE DONE UNLESS WEATHER AND SOIL CONDITIONS ARE SUITABLE

HANDLING OF SOD SHALL BE DONE IN A MANNER AS TO PREVENT TEARING, BREAKING, DRYING, OR OTHER DAMAGE.

SOD SHALL BE INSTALLED ON-SITE IN NOT MORE THAN 72 HOURS AFTER CUTTING. IF THE SOD IS NOT INSTALLED WITHIN 48 HOURS AFTER CUTTING, IT SHALL BE UNSTACKED OR UNROLLED, PLACED IN SHADE, AND KEPT MOIST UNTIL INSTALLATION.

LAY SOD PARALLEL TO THE DIRECTION OF THE SLOPE AND IN A MANNER WHICH WILL PERMIT JOINTS TO ALTERNATE.

FIT SOD PIECES TOGETHER TIGHTLY SO THAT NO JOINT IS VISIBLE, AND TAMP SOD FIRMLY AND EVENLY BY HAND.

AFTER SODDING IS COMPLETE AND APPROVED BY LANDSCAPE ARCHITECT, SODDED AREAS SHALL BE ROLLED WITH A 200 LB. ROLLER.

WATER SODDED AREAS IMMEDIATELY AFTER FINAL ROLLING WITH A FINE SPRAY TO A DEPTH OF 4 INCHES. KEEP ALL SODDED AREAS CONTINU-OUSLY MOIST THEREAFTER UNTIL 30 CALENDAR DAYS FOLLOWING INSTALLATION. USE FINE SPRAY NOZZLES ONLY.

INSPECT AND MAINTAIN SODDED AREAS AND MAKE NECESSARY REPAIRS DURING THE SPECIFIED GUARANTEE PERIOD. IF 60% OR MORE OF SODDED AREAS FAIL TO BECOME ROOTED, THE CONTRACTOR, AT NO ADDITIONAL EXPENSE TO THE OWNER, WILL REPEAT THE ENTIRE PROCESS WITH NEW SOD MATERIALS.

SEEDING: APPLY TURF-TYPE SEED MIXTURE (E.G. "CONFEDERATE" FESCUE MIXTURE, "TRI-BLEND", ETC.) AT A RATE OF 6 LBS. PER 1000 S.F. KENTUCKY 31 TALL FESCUE IS UNACCEPTABLE.

CULTIPACK SEEDED AREAS AND APPLY ANTI-EROSION MULCH AT A RATE OF

INSPECT AND MAINTAIN SEEDED AREAS AND MAKE NECESSARY REPAIRS DURING THE SPECIFIED GUARANTEE PERIOD. IF 60% OR MORE OF SEEDED AREAS FAIL TO BECOME ESTABLISHED, THE CONTRACTOR, AT NO ADDITONAL EXPENSE TO THE OWNER, WILL REPEAT THE ENTIRE PROCESS FOR ESTABLISHMENT OF A

LANDSCAPE WORK SPECIFICATIONS

IRRIGATION DIRECTIVES

- A. THE GENERAL CONTRACTOR SHALL SUBCONTRACT THE IRRIGATION WORK TO A FIRM OF HIS CHOICE. OR HAVE THE PLANTING CONTRACTOR SUB-CONTRACT THE IRRIGATION WORK TO A LICENSED IRRIGATION CONTRACTOR FIRM OF THEIR CHOICE.
- B. THE IRRIGATION SYSTEM SHALL BE DESIGNED TO SPRAY THE LAWNS AND PLANT BEDS SEPARATELY AS SHOWN ON THE PLAN IN OUTLYING AREAS ISLANDS OF SHRUBS SHALL BE OVERSPRAYED WITH THE LAWN HEADS OR, PER PLAN, MAY HAVE SHRUB HEADS ON THE ADJACENT LAWN ZONE
- C. PROVIDE ADEQUATE ZONES TO INDIVIDUALLY CONTROL IRRIGATION FOR ALL THE DIFFERENT EXPOSURES AND SLOPES AT LEAST AS INDICATED ON THE PLANS AS WELL AS TO BE ABLE TO BEST MATCH THE WATER AVAILABLE TO THE SYSTEM
- D. SUBMIT HEAD LAYOUT AND ROUTING PLAN TO THE LANDSCAPE ARCHITECT FOR APPROVAL OF THE LAYOUT AND ZONE DESIGN
- E. IN MUNICIPAL AREAS PROVIDE THE OWNER A (DOLLAR) CHOICE TO SET A SEPARATE METER FOR THE IRRIGATION. OR TO USE THE EXISTING METERED SOURCE FOR THE IRRIGATION
- F. METERS ARE PROVIDED FOR IRRIGATIONS; CONTRACTOR TO PROVIDE BACK-FLOW PREVENTION
- G. PROVIDE THE OWNER A PLASTIC COVERED COLOR CODED PLAN TO PLACE
- H. PROVIDE (3) THREE COPIES OF "AS-BUILT" LAYOUT AND OPERATING INSTRUCTIONS TO THE OWNER.

IRRIGATION NOTES

NEAR THE CONTROLLER

OTICE TO IRRIGATION CONTRACTOR: MANY GOVERNMENTAL UNITS ARE CURRENTLY REVISING THEIR ORDINANCES AND REGULATIONS REGARDING IRRIGATION SYSTEMS. BEFORE THIS PROJECT IS BID OR INSTALLED. THE CONTRACTOR SHALL VERIFY WITH THE RULING GOVERNMENTAL UNIT THAT THE PROPOSED SYSTEM MEETS ALL LOCAL REGULATIONS. AREAS OF SPECIAL CONCERN INCLUDE: 1. RIGHT-OF-WAY EASEMENT AGREEMENTS FOR PLACEMENT OF IRRIGATION WITHIN

- STREET/ROAD RIGHT-OF-WAYS 2. BACKFLOW PREVENTION DEVICES, WHETHER THESE ARE REQUIRED AND IF SO, WHAT TYPES
- ARE APPROVED 3. CERTIFICATION/LICENSE TO INSTALL BACKFLOW PREVENTER DEVICES AND METERS.
- 4. "WINTER SERVICE" REQUIREMENTS FOR BACKFLOW PREVENTER DEVICES. 5. USE OF A SECOND METER FOR IRRIGATION USE ONLY.
- 6. WATER RATION DAYS IN WHICH IRRIGATION SYSTEM CANNOT BE USED. 7. ALL OTHER REGULATIONS NOT MENTIONED HEREIN.

SHOULD THE BID/CONSTRUCTION DOCUMENTS BE INCONSISTANT WITH CURRENT LOCAL REGULATIONS, THE CONTRACTOR SHALL PRESENT THE OWNER WITH A QUOTE/CONTRACT THAT INCLUDES MODIFICATIONS TO MAKE THE SYSTEM COMPLIANT WITH ALL THE LOCAL CODES.

PERMITS, FEES: THE IRRIGATION CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS NECESSARY TO INSTALL THE SYSTEM AND HE SHALL PAY ANY ASSOCIATED FEES. COST FOR THESE ITEMS SHALL BE INCLUDED IN THE QUOTE/CONTRACT FOR THE IRRIGATION SYSTEM.

IRRIGATION DIRECTIVES AND NOTES

1. THE PLANTING PROCESS IS SIMILAR FOR DECIDUOUS AND EVERGREEN TREES.


. FOR SINGLE STEM TREES. DO NOT SUPPLY TREES WITH MULTIPLE LEADERS. ONLY PROVIDE TREES WITH. SINGLE LEADER. DO NOT PRUNE TREE AT PLANTING EXCEPT FOR SPECIFIC STRUCTURAL CORRECTIONS AND TO INSURE COMPLIANCE WITH SIGHT DISTANCE STANDARDS.

3. MARK THE NORTH SIDE OF THE TREE AT THE NURSERY AND LOCATE TO THE NORTH IN THE FIELD.

4. WHERE SEVERAL TREES WILL BE PLANTED CLOSE TOGETHER SUCH THAT THEY WILL LIKELY SHARE ROOT SPACE. TILL IN SOIL AMENDMENTS TO A DEPTH OF 6" TO 8" OVER THE ENTIRE BED AREA. 5. FOR CONTAINER-GROWN TREES, SET THE ROOTS OUT OF THE OUTER LAYER OF POTTING SOIL, THEN CUT OR

PULL APART ANY ROOTS CIRCLING THE PERIMETER OF THE CONTAINER. 6. THOROUGHLY SOAK THE TREE ROOT BALL AND ADJACENT PREPARED SOIL SEVERAL TIMES DURING THE FIRST MONTH AFTER PLANTING AND REGULARLY THROUGHOUT THE FOLLOWING TWO SUMMERS.

7. IF PLANTING HOLES ARE DUG WITH A LARGE AUGER. BREAKING DOWN THE SIDES WITH A SHOVEL TO



*FOR BOTH CANOPY OR UNDERSTORY STREES * TYPICAL TREE INSTALLATION


MASSING PLANT INSTALLATION


UNDISTURBED

SUBGRADE


Town Certification. This design has been reviewed by the Engineer for the Town of Knightdale, and to the best of my knowledge and belief, it conforms to the requirements established in the Standard Specifications of the Town of Knightdale.

Town Engineer These plans are approved by the Town of Knightdale and serve as





BED EDGING



ON CENTER (O.C.)

DIMENSION VARIES

SEE PLAN

CONTRACTOR SHALL PRUNE

CAMBIUM EDGE CLEAN.

3-4" THK. LAYER OF -

TRIPLE SHREDDED

HARDWOOD MULCH

MACHINE OR SPADE

CRISP TRANSITION AT

FDGING: PROVIDE

HAND TAMPED

PLANTING MIXTURE

(SEE SPECS)

APPROVED BACKFILL

1/2 LB. 10-10-10 FERTILIZER

PER CU. YD. OF BACKFILL

CROWDED, BROKEN, OR STRAY

BRANCHES. CUT FLUSH, LEAVING

*FOR BOTH CONTAINER OR B&B SHRUBS

FORM SAUCER

2" DEEP TO

CROWN PLANTING BED

AT 10% PITCH OR 4" MIN.

HOLD WATER

*TYPICAL SHRUB INSTALLATION

REVISED 9:36 am, Jan 26, 2022

NOT RELEASED FOR CONSTRUCTION

ADS/BRI IORIZONTAL SCA SEE GRAPHIC SCALE RTICAL SCALE *N/A*

02/24/2017

TOK SU-2-01