5201 KNIGHTDALE EAGLE ROCK ROAD

SITE DATA TABLE	
TOTAL SITE AREA	201.3 ACRES
PROJECT LOCATION	5201 KIGHTDALE EAGLE ROCK ROAD, MARKS CREEK, WAKE COUNTY, NORTH CAROLINA
KNIGHTDALE ZONING	DUKE ENERGY PROGRESS; ZONING: MI
EXISTING ZONING	MI
EXISTING LAND USE	UTILITIES - CLASS 1 & 2 (SUBSTATION)
PROPOSED LAND USES	UTILITIES - CLASS 1 & 2 (BATTERY STORAGE FACILITY)
RIVER BASIN	NEUSE RIVER
RECEIVING WATER	MARK'S CREEK
WATERSHED CLASSIFICATION	C; NSW
PROPOSED BATTERY UNITS	60
INFRASTRUCTURE	TOTAL 201.3 ACRES, BESS FACILITY 11.3 ACRES
IMPERVIOUS AREA	4.7 ACRES
DISTURBED AREA	11.4 ACRES
PROPERTY OWNER 1	DUKE ENERGY PROGRESS INC.
SITE PARKING	SUBSTATION YARD OR OUTSIDE THE GATE
SETBACK TO WEST PROPERTY LINE	150'-0"
SETBACK TO NORTHERN RIGHT OF WAY	450'-0"

PHASING AND TIMETABLE TREE CUTTING START DATE 01-NOV-24 SITE CIVIL WORK START DATE 02-DEC-24 PLANNED STATE OF COMPLETION 30-SEP-25

SUPPLEMENTAL REGULATIONS 5.10.H - GRID SCALE BATTERY STORAGE FACILITIES (UNIFIED DEVELOPMENT ORDINANCE)

- 1. NO GRID-SCALE BATTERY STORAGE FACILITY SHALL BE LOCATED WITHIN A ONE HUNDRED (100) FOOT RADIUS OF THE FOOTPRINT OF ANY PRE-EXISTING ADJACENT RESIDENTIAL DWELLING
- 2. GRID—SCALE BATTERY STORAGE FACILITIES SHALL ONLY BE PERMITTED WHEN CO—LOCATED ON A
- 3. A TYPE D BUFFER YARD SHALL BE REQUIRED ON ALL SIDES OF A GRID-SCALE BATTERY STORAGE FACILITY ADJACENT TO A RESIDENTIAL ZONING DISTRICT. ALL OTHER REQUIRED BUFFER YARDS SHALL BE CONSISTENT WITH SECTION 7.4 (1)(1).
- 4. ALL SIDES OF A GRID—SCALE BATTERY STÒRÀGE FACILITY SHALL BE SCREENED FROM OFF—SITE VIEW BY USE OF A FENCE OR MASONRY WALL. THE MATERIALS OF THE FENCE OR MASONRY WALL SHALL BE CONSISTENT WITH THOSE LISTED IN SECTION 7.6 (C). THE HEIGHT OF ANY FENCE OR MASONRY WALL SHALL BE CONSISTENT WITH THE HEIGHT OF THE ENERGY STORAGE CONTAINER. THE MAXIMUM HEIGHT OF SUCH FENCE OR MASONRY WALL SHALL NOT EXCEED 8 FEET IN HEIGHT REGARDLESS OF THE HEIGHT OF THE ENERGY STORAGE CONTAINER.
- 5. THE GRID—SCALE BATTERY STORAGE FACILITY SHALL HAVE AT LEAST ONE ENTRANCE OF SUFFICIENT DESIGN TO ALLOW FOR THE PROVISION OF EMERGENCY SERVICES, AS APPROVED BY THE KNIGHTDALE FIRE DEPARTMENT.
- 6. PRIOR TO CONSTRUCTION DRAWING APPROVAL, A THIRD-PARTY NOISE ANALYSIS SHALL BE SUBMITTED ESTABLISHING THAT THE GRID-SCALE BATTERY STORAGE FACILITY AS DESIGNED WILL NOT EXCEED NOISE LEVEL LIMITS AT THE PROPERTY LINE(S) SET FORTH IN THE APPLICABLE NOISE ORDINANCE.
- 7. THE NOISE LEVEL LIMITS APPLICABLE TO THE GRID-SCALE BATTERY STORAGE FACILITY SHALL BE DETERMINED BY THE LOCATION OF THE FACILITY. IF THE FACILITY IS LOCATED IN TOWN LIMITS, THE NOISE LEVEL LIMITS SET FORTH IN THE TOWN'S CODE OF ORDINANCES (KNIGHTDALE NOISE ORDINANCE) SHALL APPLY. IF THE FACILITY IS LOCATED OUTSIDE OF TOWN LIMITS BUT WITHIN THE TOWN'S EXTRA-TERRITORIAL JURISDICTION, THE NOISE LEVEL LIMITS SET FORTH IN WAKE COUNTY'S CODE OF ORDINANCES SHALL APPLY.
- 8. AN ADDITIONAL NOISE ANALYSIS SHALL BE REQUIRED IF THE FACILITY EXCEEDS THE APPLICABLE NOISE LEVEL LIMITS. IF WARRANTED BY THE NOISE ANALYSIS, NOISE DAMPENING MEASURE SHALL BE INSTALLED IN ANY AREA THAT PRODUCES EXCESSIVE NOISE.

TOWN APPROVED STANDARDS SHALL CONTROL IN THE EVENT OF A CONFLICT OR INCONSISTENCY BETWEEN THESE CONSTRUCTION DRAWING AND THE TOWN OF KNIGHTDALE'S APPROVED STANDARDS FOR THIS PROJECT, THE APPROVED STANDARDS SHALL CONTROL. TOWN OF KNIGHTDALE APPROVED STANDARDS SHALL MEAN ALL DEVELOPMENT DOCUMENTS NECESSARY FOR APPROVAL FOR THE PROPERTY INCLUDING, BUT NOT LIMITED TO, ANY SPECIAL USE PERMIT, SUBDIVISION PLAN, SITE PLAN, SUBDIVISION PLAT(S), PHASING SCHEDULE, DEVELOPMENT AGREEMENT, UTILITY ALLOCATION AGREEMENT, ANNEXATION AGREEMENT, THE TOWN OF KNIGHTDALE STANDARD SPECIFICATION AND DETAILS MANUAL AND APPLICABLE PROVISIONS OF THE NORTH




CAROLINA STATE BUILDING CODE.

PROFESSIONAL DESIGN ENGINEER CERTIFICATION: BESS ELECTRICAL


THESE IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING DRAWINGS AND WITH THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE. I, OLUFEMI OYEBANJO, PE, CERTIFY THAT THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE HAVE BEEN THOROUGHLY CHECKED AND FOUND TO BE APPLICABLE TO THIS PROJECT. ALL EXCEPTIONS TO THE TOWN STANDARDS HAVE BEEN PREVIOUSLY APPROVED BY THE TOWN OF KNIGHTDALE AND SAID EXCEPTIONS ARE SHOWN ON SHEET(S) ______ OF THESE DRAWINGS.

KNIGHTDALE, NC 27545 TOK PROJECT # ZCP-3-23





SITE VICINITY MAP





PROFESSIONAL DESIGN ENGINEER CERTIFICATION: CIVIL THESE IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING DRAWINGS AND WITH THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE. I, HANNAH ULRICH, PE, CERTIFY THAT THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE HAVE BEEN THOROUGHLY CHECKED AND FOUND TO BE APPLICABLE TO THIS PROJECT. ALL EXCEPTIONS TO THE TOWN STANDARDS HAVE BEEN PREVIOUSLY APPROVED BY THE TOWN OF KNIGHTDALE AND SAID EXCEPTIONS

ARE SHOWN ON SHEET(S) _____ OF THESE DRAWINGS.



PROFESSIONAL DESIGN ENGINEER CERTIFICATION: SUBSTATION ELECTRICAL THESE IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING DRAWINGS AND

WITH THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE. I, ETAHN BROWN, PE, CERTIFY THAT THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE HAVE BEEN THOROUGHLY CHECKED AND FOUND TO BE APPLICABLE TO THIS PROJECT. ALL EXCEPTIONS TO THE TOWN STANDARDS HAVE BEEN PREVIOUSLY APPROVED BY THE TOWN OF KNIGHTDALE AND SAID EXCEPTIONS ARE SHOWN ON SHEET(S) ______ OF THESE DRAWINGS.

CONTACT LIST		
CONTACTS	NAME	ADDRESS
OWNER	DUKE ENERGY PROGRESS, LLC	7804 FAIRVIEW ROAD, SUITE C BOX 214, CHARLOTTE, NC 28226 ATTN: GREG MCELMURRY, PHONE: 704-264-9879
ELECTRICAL ENGINEER (SUBSTATION)	ETHAN BROWN	175 REGENCY WOODS PLACE, SUITE 300, CARY, NC 24515-0000
ELECTRICAL ENGINEER (BESS)	OLUFEMI OYEBANJO	920 MEMORIAL CITY WAY, SUITE 600, HOUSTON, TX 77024
CIVIL ENGINEER	HANNAH ULRICH	11401 LAMAR AVENUE, OVERLAND PARK, KS 66211

DRAWING NUMBER:	DRAWING NAME:	DRAWING SET:
KND01-CV-C-SI.CS-01	COVER SHEET	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-SI.PL-02	ENVIRONMENTAL SURVEY	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-SI.PL-01	SITE PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-AD-A-YD.00.PL-02	LANDSCAPE PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-LT-E-PL-01	BESS ELECTRICAL LIGHTING PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-LT-E-PL-02	ELECTRICAL LIGHTING STUDY OVERALL BESS SITE	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-LT-E-SD-01	ELECTRICAL LIGHTING DETAILS	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND00-LT-E-SY.00.PL-01	ELECTRICAL LIGHTING PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND00-LT-E-SY.00.SD-01	ELECTRICAL LIGHTING DETAILS	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-FE.PL-01	SURFACING AND FENCING PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-FE.SD-01	FENCING DETAILS	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-GR.SD-01	SURFACING DETAILS	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-GR.SD-02	GRADING DETAILS	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-GR.SD-04	GRADING DETAILS	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-AD-A-YD.00.PL-01	ARCHITECTURAL PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-AD-A-YD.00.SD-01	ARCHITECTURAL ELEVATION AND SECTIONS	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-AD-A-YD.00.SD-02	DIGITAL MATERIALS BOARD	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-VEN-LG-E-SD-01	BESS CONTAINER ARCHITECTURAL PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-VEN-LG-E-SD-02	MVT SKID ARCHITECTURAL PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-VEN-LG-AE.00.SD-03	SITE CONTROL CENTER ARCHITECTURAL PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND00-GA-M-SY.00.EV-01	SUBSTATION CONTROL ENCLOSURE ARCHITECTURAL PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-UG-E-PL-01	ELECTRICAL UNDERGROUND CONDUIT BESS OVERALL	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-GR.PL-01	STORMWATER MANAGEMENT PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-GR.PL-02	STORMWATER MANAGEMENT PLAN	TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS
KND01-CV-C-SI.CS-01	COVER SHEET	NCDEQ APPROVED
KND01-CV-C-SI.PL-02	ENVIRONMENTAL SURVEY	NCDEQ APPROVED
KND01-CV-C-SI.PL-01	SITE PLAN	NCDEQ APPROVED
KND01-CV-C-GR.PL-01	GRADING & DRAINAGE PLAN	NCDEQ APPROVED
KND01-CV-C-GR.PL-02	GRADING & DRAINAGE PLAN	NCDEQ APPROVED
KNDO1-CV-C-EC.PL-01	EROSION & SEDIMENT CONTROL PLAN	NCDEQ APPROVED
KNDO1-CV-C-EC.PL-02	EROSION & SEDIMENT CONTROL PLAN	NCDEQ APPROVED
KND01-CV-C-EC.SD-01	EROSION & SEDIMENT CONTROL DETAILS	NCDEQ APPROVED
KND01-CV-C-EC.SD-02	EROSION & SEDIMENT CONTROL DETAILS	NCDEQ APPROVED
KND01-CV-C-EC.SD-03	EROSION & SEDIMENT CONTROL NOTES	NCDEQ APPROVED
KND01-CV-C-EC.SD-04	EROSION & SEDIMENT CONTROL NOTES	NCDEQ APPROVED
KND01-CV-C-FE.PL-01	FENCING PLAN	NCDEQ APPROVED

NOTE: DRAWINGS DESIGNATED 'NCDEQ APPROVED' ARE ISSUED FOR REFERENCE ONLY TO SHOW THE APPROVED DESIGN OF EROSION AND SEDIMENT CONTROL MEASURES.TOWN OF KNIGHTDALE CONSTRUCTION DRAWINGS INCLUDE MORE RECENT REVISIONS AND CONTROL FOR CONSTURCTION OF ALL PERMANENT FACILITIES WHILE MAINATAINING COMPLIANCE WITH NCDEQ APPROVAL OF TEMPORARY EROSION CONTROL MEASURES.

TOWN CERTIFICAITON
THIS DESIGN HAS BEEN REVIEW BY THE ENGINEER FOR THE TOWN OF KNIGHTDALE, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF, IT CONFORMS TO THE REQUIREMENTS ESTABLISHED IN THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE.

BY: _____ DATE: _____
TOWN ENGINEER

THESE PLANS ARE APPROVED BY THE TOWN OF KNIGHDALE AND SERVE AS CONSTRUCTION PLANS FOR THIS PROJECT.

LAND USE ADMINISTRATOR


ISSUED FOR


THE DISTRIBUTION AND USE OF THE NATIVE FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST CONTROLLED VERSION.


	70111111111111111111111111111111111111							1/13/2025	
13/JAN/2025	ISSUED FOR PERMITTING	CLC	MJM	1HGU	WL	Е	27/SEP/2024	ISSUED FOR PERMITTING	CLC MJMHGUDSLD
20/DEC/2024	ISSUED FOR PERMITTING	CLC	MJM	1HGU	WL	D	24/SEP/2024	ISSUED FOR PERMITTING	CLC MJMHGUDSLD
21/NOV/2024	90% SUBMITTAL	CLC	MJM	1HGU	WL	С	12/SEP/2024	ISSUED FOR PERMITTING	CLC MJMHGUDSLD
18/NOV/2024	ISSUED FOR PERMITTING	CLC	MJM	1HGU	WL	В	4/SEP/2024	ISSUED FOR 60% REVIEW	CLC MJMHGUDSLD
25/OCT/2024	ISSUED FOR PERMITTING	CLC	MJM	1HGU	DSLD	NO	DATE	REVISIONS AND RECORD OF ISSUE	DRN DES CHK PDE APP


R _o	BLAC Building	CK&V	EATCH f difference.	•
DESIGNER	MJM	DRAWN	CLC	
CHECKED		DATE		1


DUKE DUKE ENERGY	PROJECT	DRAWING NUMBER	REV
DUKE ENERGY ENERGY KNIGHTDALE BATTERY ENERGY STORAGE SYSTEM	419596 K	ND01-CV-C-SI.CS-01	J
COVER SHEET	CODE		•
5201 KNIGHTDALE EAGLE ROCK ROAD KNIGHTDALE NC 27545	AREA	1	





















Lun	ninaire	Location	ıs
No.	Label	МН	Tilt
1	Α	10'-6"	0.00
2	Α	10'-6"	0.00
3	Α	10'-6"	0.00
4	Α	10'-6"	0.00
1	В	23'-6"	30.00
2	В	23'-6"	30.00
3	В	23'-6"	25.00
4	В	23'-9"	40.00
5	В	23'-0"	20.00
6	В	23'-9"	45.00
7	В	23'-0"	25.00
8	В	23'-0"	45.00
9	В	23'-9"	45.00
10	В	23'-9"	45.00
11	В	23'-0"	45.00

Schedul	e												
Symbo	Label	Quantity	Manufacturer	Catalog Number	Description	Number Lamps	Filename	Lumens Per Lamp	Lumen Multiplier	Light Loss Factor	Efficiency	Wattage	Distribution
	Α	4	COOPER LIGHTING SOLUTIONS - LUMARK (FORMERLY EATON)	XTOR2B-Y	CROSSTOUR WALL MOUNT LED	1	XTOR2B-Y.ies	1997	1	0.85	100%	18.2	
	В	11	American Electric Lighting	ACPOLED P40 XXXXX 55 ACPOLEDFV	ACP Small LED Floodlight with P40 Performance Package, Flood (5x5) (formally FL), 4000K CCT, 70CRI with Full Visor	1	ACPOLED P40 XXXXX 55 ACPOLEDFV.ies	Absolute	1	0.85	100%	154	5 X 5

Statistics					
Description	Symbol	Max	Min	Avg	AVERAGE TO MINIMUM FC RATIO
Substation	+	28.8 fc	0.1 fc	5.2 fc	52
Perimeter	+	12.0 fc	0.0 fc	0.4 fc	-



1. FIELD TO CONFIRM SUFFICIENT LIGHT ORIENTATION AND ILLUMINATION LEVELS WITH DUKE PERSONNEL.

TOWN CERTIFICATION
THIS DESIGN HAS BEEN REVIEW BY THE ENGINEER FOR THE TOWN OF KNIGHTDALE, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF, IT CONFORMS TO THE REQUIREMENTS ESTABLISHED IN THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE.

BY: _______TOWN_ENGINEER

THESE PLANS ARE APPROVED BY THE TOWN OF KNIGHDALE AND SERVE AS CONSTRUCTION PLANS FOR THIS PROJECT.

BY: _____LAND_USE_ADMINISTRATOR

ISSUED FOR PERMITTING


THE DISTRIBUTION AND USE OF THE NATIVE FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST


								5/DEC/24	ISSUED FOR 90% REVIEW	BCA BCA	VC	BCA	۱ E	RB
								15/NOV/24	ISSUED FOR PERMIT	BCA BCA	VC	BCA	4 E	.RB
								3 29/AUG/24	ISSUED FOR 60% REVIEW	BCA BCA	VC	BC₽	4 E	RB
							,	A 23/AUG/24	ISSUED FOR PERMIT	BCA BCA	VC	BC₽	4 E	:RB
Е	18/DEC/24	ISSUED FOR PERMIT	ВСА	ВСА	۱ ۲	VC BCA E	RB N	O DATE	REVISIONS AND RECORD OF ISSUE	DRN DES	СНК	PDF	ĒΑ	۱PP


BLACI	K&VEATCH	•
DESIGNER	DRAWN	
BCA	BCA	
CHECKED	DATE	


CONTROLLED VERSION.			
DUKE ENERGY	PROJECT	DRAWING NUMBER	REV
KNIGHTDALE BATTERY ENERGY STORAGE SYSTEM	KND00-LT-E	-SY.00.PL-01	Ε
ELECTRICAL LIGHTING PLAN	CODE		
5201 KNIGHTDALE EAGLE ROCK ROAD KNIGHTDALE, NC 27545	AREA	1	


SCALE: 1" = 20'-0"


















SECTION A TYPICAL PANEL / POST CONNECTION SCALE: 1" = 6"

NOTE:

1. THE DECORATIVE WALL WITH FOUNDATION WILL BE DESIGNED BY THE MANUFACTURER.



BRICK FINISH

TOWN CERTIFICATION
THIS DESIGN HAS BEEN REVIEW BY THE ENGINEER FOR THE TOWN OF KNIGHTDALE, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF, IT CONFORMS TO THE REQUIREMENTS ESTABLISHED IN THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE.

THESE PLANS ARE APPROVED BY THE TOWN OF KNIGHDALE AND SERVE AS CONSTRUCTION PLANS FOR THIS PROJECT.

BY: _____LAND USE ADMINISTRATOR


ISSUED FOR PERMITTING THE DISTRIBUTION AND USE OF THE NATIVE

FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST CONTROLLED VERSION.





		· · · · · · · · · · · · · · · · · · ·
ΔA	D 13/JAN/2025 ISSUED FOR PERMITTING CLCMJMHGU WL - I HEREBY CERTIFY THAT THIS DOCUMENT WAS PREPARED BY ME OR UNDER MY DIRECT SUPER- PREPARED BY ME OR UNDER MY DIRECT SUPER- DUKE ENERGY	PROJECT DRAWING NUMBER REV
22 7:29	CLCM//MHGU WL - PREPARED BY ME OR UNDER MY DIRECT SUPER- VISION AND THAT I AM A DULY REGISTERED PRO- VISION AND THAT I AM A DULY REGISTERED PRO- SINGLE SUPER LAWS OF THE LAWS	419596 KND01-AD-A-YD.00.SD-01 D
34x2 34x2 324	B 21/NOV/24 90% SUBMITTAL JCB WL STATE OF - DESIGNER DRAWN DCV ARCHITECTURAL ELEVATION AND ARCHITECTURAL ELEVATION ARCHITECTURAL ELEVATION ARCHITECTURAL ELEVATION ARCHITECTURAL ELEVATION ARCHITECTURAL ELEVATION ARCHITECTURAL ELEVATION ARCHITECTURAL	ND SECTIONS CODE
5/20 5/20	A 26/AUG/24 ISSUE FOR PERMITTING DCV - DSD DSD - SIGNED - DCV - DSD DSD - DSD DSD - DSD DSD - DSD DSD	1D SECTIONS
COP ANS 8/15	NO DATE REVISIONS AND RECORD OF ISSUE DRN DES CHK PDE APP DATE HGU DATE 13/JAN/25	AREA

Cop113378 ANSI D 34x22 8/15/202/ 7:2



BLAC 11401 LAMAR AV ® OVERLAND PARI		DUKE ENERGY KNIGHTDALE BATTERY ENERGY STORAGE SYSTEM	RND01-VE	DRAWING NUMBER N-LG-E-SD-01	B REV	
R BCA	DRAWN RSN	BESS CONTAINER ARCHITECTURAL PLAN	CODE		_	
DATE		5201 KNIGHTDALE EAGLE ROCK ROAD	ARFA	1		ı







MVS5140-LS-US

MV Turnkey Solution for PowerTitan 2.0 MVS Liquid Cooling Energy Storage System



Product Name	MVS5140-LS-US
MV transformer	
Rated power	5140 kVA
MV / LV voltage	34.5 kV / 0.69 kV
Transformer vector	Dyl
Windings	2 windings
Rated frequency	60 Hz
Impedance	9 % (± 7.5 %, IEEE tolerance)
Efficiency standard	99 % @ 100 % load
Material of winding (MV / LV)	Aluminum / Aluminum
Legged core design	3 Legged core Design
High voltage configuration	Loop-feed, Dead Front
Overcurrent protection	Expulsion fuses in series with Partial-Range Current-Limiting Fuses
Cooling method	KNAN
Insulation fluid	Degradable oil
Smart control cabinet	
Protection	AC Breaker
Surge protection	Type II
AC Insulation detection	Support
Cooling Method	Air cooling and HVAC
LIDG	15 min (Default)
UPS	2/3/4h (Optional)
General data	
Dimensions (W*H*D)	6058 mm * 2896 mm * 2438 mm
Difficultions (VV Tr D)	238.5'' * 114.0'' * 96.0''
NA/a i a la t	15300 kg
Weight	33730 lbs
Cable entry	Bottom entry
Degree of protection	Type 3S
Anti-corrosion degree	C4
	-40 °C ~ 60 °C
Operation temperature range	-40 °F ~ 140 °F
Operation temperature range	> 40 °C (104 °F) derating (Default)
	> 45 °C (113 °F) derating (Optional)
Operation humidity range	0 % ~ 100 %
Max. operating altitude	3000 m
	9842.5 ft
Communication	Ethernet, Optical fiber, RS485
Standard	UL 891, IEEE C57.12.00, IEEE C57.12.80, IEEE C57.12.90

© 2024 Sungrow Power Supply Co., Ltd. All rights reserved. Subject to change without notice. Version 1



THIS DESIGN HAS BEEN REVIEWED BY THE ENGINEER FOR THE TOWN OF KNIGHTDALE, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF, IT CONFORMS TO THE REQUIREMENTS ESTABLISHED IN THE STANDARD SPECIFICATIONS OF THE TOWN OF KNIGHTDALE

THESE PLANS ARE APPROVED BY THE TOWN OF KNIGHTDALE AND SERVE AS CONSTRUCTION PLANS FOR THIS PROJECT.

LAND USE ADMINISTRATOR

ISSUED FOR PERMITTING


FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST


""""""""""""""""""""""""""""""""""""""	2,110,002,10111		CONTROLLED VERSION	•	B&V PROJECT NUMBER	R: 419596
DI A	CK & VE ATCH	DUKE	DUKE ENERGY	PROJECT	DRAWING NUMBER	REV
BLACK & VEATCH 11401 LAMAR AVENUE OVERLAND PARK, KANSAS 66211		C ENERGY.	MVT SKID LAYOUT	KND01-VEN	KND01-VEN-LG-E-SD-02	
DESIGNER BCA	DRAWN RSN	F.	MVT SKID ARCHITECTURAL PLAN	CODE		
CHECKED	DATE	52	201 KNIGHTDALE EAGLE ROCK ROAD KNIGHTDALE NC 27545	AREA		


REVISIONS AND RECORD OF ISSUE


| RSN | BCA | OOO | OOO | B |DRN| DES | CHK | PDE | APF


^{* 15}min UPS only supplies power for the control and communication devices in the MVS ** 2/3/4 h UPS supplies power for the control and communication devices in the the MVS, and the ventilation system in the battery container




















KNIGHTDALE PROPOSED BATTERY ENERGY STORAGE FACILITY 5201 KNIGHTDALE EAGLE ROCK ROAD KNIGHTDALE, NC 27545 TOK PROJECT # ZCP-3-23

SITE DATA TABLE	
TOTAL SITE AREA	201.3 ACRES
PROJECT LOCATION	5201 KIGHTDALE EAGLE ROCK ROAD, MARKS CREEK, WAKE COUNTY, NORTH CAROLINA
KNIGHTDALE ZONING	DUKE ENERGY PROGRESS; ZONING: MI
PROPOSED ZONING	MI
EXISTING LAND USE	UTILITIES - CLASS 1 & 2 (SUBSTATION)
PROPOSED LAND USES	UTILITIES - CLASS 1 & 2 (BATTERY STORAGE FACILITY)
RIVER BASIN	NEUSE RIVER
RECEIVING WATER	MARK'S CREEK
WATERSHED CLASSIFICATION	C; NSW
PROPOSED UNITS	60
INFRASTRUCTURE	TOTAL 201.3 ACRES, BESS FACILITY 11.3 ACRES
IMPERVIOUS AREA	4.7 ACRES
DISTURBED AREA	11.4 ACRES
PROPERTY OWNER 1	DUKE ENERGY PROGRESS INC.
SITE PARKING	SUBSTATION YARD OR OUTSIDE THE GATE

PHASING AND TIMETABLE							
TREE CUTTING START DATE	01-NOV-24						
SITE CIVIL WORK START DATE	02-DEC-24						
PLANNED STATE OF COMPLETION	30-SEP-25						

SUPPLEMENTAL REGULATIONS 5.10.H - GRID SCALE BATTERY STORAGE FACILITIES (UNIFIED DEVELOPMENT ORDINANCE)

- 1. NO GRID—SCALE BATTERY STORAGE FACILITY SHALL BE LOCATED WITHIN A ON HUNDRED (100) FOOT RADIUS OF THE FOOTPRINT OF ANY PRE—EXISTING ADJACENT RESIDENTIAL DWELLING 2. GRID—SCALE BATTERY STORAGE FACILITIES SHALL ONLY BE PERMITTED WHEN CO—LOCATED ON A
- SITE WITH A SUBSTATION FACILITY.


 3. A TYPE D BUFFER YARD SHALL BE REQUIRED ON ALL SIDES OF A GRID—SCALE BATTERY STORAGE FACILITY ADJACENT TO A RESIDENTIAL ZONING DISTRICT. ALL OTHER REQUIRED BUFFER YARDS
- SHALL BE CONSISTENT WITH SECTION 7.4 (I)(1).


 4. ALL SIDES OF A GRID—SCALE BATTERY STORAGE FACILITY SHALL BE SCREENED FROM OFF—SITE VIEW BY USE OF A FENCE OR MASONRY WALL. THE MATERIALS OF THE FENCE OR MASONRY WALL SHALL BE CONSISTENT WITH THOSE LISTED IN SECTION 7.6 (C). THE HEIGHT OF ANY FENCE OR MASONRY WALL SHALL BE CONSISTENT WITH THE HEIGHT OF THE ENERGY STORAGE CONTAINER. THE MAXIMUM HEIGHT OF SUCH FENCE OR MASONRY WALL SHALL NOT EXCEED 8 FEET IN HEIGHT DECLARDIESS OF THE HEIGHT OF THE ENERGY STORAGE CONTAINER.
- REGARDLESS OF THE HEIGHT OF THE ENERGY STORAGE CONTAINER.

 5. THE GRID—SCALE BATTERY STORAGE FACILITY SHALL HAVE AT LEAST ONE ENTRANCE OF SUFFICIENT DESIGN TO ALLOW FOR THE PROVISION OF EMERGENCY SERVICES, AS APPROVED BY THE
- KNIGHTDALE FIRE DEPARTMENT.

 6. PRIOR TO CONSTRUCTION DRAWING APPROVAL, A THIRD—PARTY NOISE ANALYSIS SHALL BE SUBMITTED ESTABLISHING THAT THE GRID—SCALE BATTERY STORAGE FACILITY AS DESIGNED WILL NOT EXCEED NOISE LEVEL LIMITS AT THE PROPERTY LINE(S) SET FORTH IN THE APPLICABLE NOISE
- 7. THE NOISE LEVEL LIMITS APPLICABLE TO THE GRID-SCALE BATTERY STORAGE FACILITY SHALL BE DETERMINED BY THE LOCATION OF THE FACILITY. IF THE FACILITY IS LOCATED IN TOWN LIMITS, THE NOISE LEVEL LIMITS SET FORTH IN THE TOWN'S CODE OF ORDINANCES (KNIGHTDALE NOISE ORDINANCE) SHALL APPLY. IF THE FACILITY IS LOCATED OUTSIDE OF TOWN LIMITS BUT WITHIN THE TOWN'S EXTRA—TERRITORIAL JURISDICTION, THE NOISE LEVEL LIMITS SET FORTH IN WAKE COUNTY'S
- CODE OF ORDINANCES SHALL APPLY.

 8. AN ADDITIONAL NOISE ANALYSIS SHALL BE REQUIRED IF THE FACILITY EXCEEDS THE APPLICABLE NOISE LEVEL LIMITS. IF WARRANTED BY THE NOISE ANALYSIS, NOISE DAMPENING MEASURE SHALL BE INSTALLED IN ANY AREA THAT PRODUCES EXCESSIVE NOISE.





1"=4000'

CONTACTS	NAME	ADDRESS
OWNER	DUKE ENERGY PROGRESS, LLC	7804 FAIRVIEW ROAD, SUITE C BOX 214, CHARLOTTE, NC 28226 ATTN: GREG MCELMURRY, PHONE: 704-264-9879
ELECTRICAL ENGINEER (SUBSTATION)	ETHAN BROWN	175 REGENCY WOODS PLACE, SUITE 300, CARY, NC 24515-0000
ELECTRICAL ENGINEER (BESS)	OLUFEMI OYEBANJO	920 MEMORIAL CITY WAY, SUITE 600, HOUSTON, TX 77024
STRUCTURAL ENGINEER	DIVYA SRI LAKSHIMI DINAVAHI	2880 ZANKER RD STE 203, SAN JOSE, CA 95134
CIVIL ENGINEER	HANNAH ULRICH	11401 LAMAR AVENUE, OVERLAND PARK, KS 66211

ISSUED FOR PERMITTING
THE DISTRIBUTION AND USE OF THE NATIVE FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST

CONTROLLED VERSION.




NOTE: THE INFORMATION ON THIS SHEET WAS PREPARED BY ERM NC, INC. ON 05/09/2023 AND MODIFIED BY BLACK & VEATCH


			D	24/SEP/2024	ISSUED FOR PERMITTING	СГС М Ј М Н С	gups	LD	
			С	12/SEP/2024	ISSUED FOR PERMITTING	CLC MJMHG	gups	LD	
			В	4/SEP/2024	ISSUED FOR 60% REVIEW	CLC MJMHG	gubs	LD	
			Α	23/AUG/2024	ISSUED FOR PERMITTING	СГС М Ј М Н С	gups	LD	
		١	NO	DATE	REVISIONS AND RECORD OF ISSUE	DRN DES CH	нк рг)E A	٩P


R _®	BLAC Building a	K & VEATCH world of difference.	DUKE ENERGY, KI
DESIGNER	МЈМ	DRAWN CLC	51
CLIECKED		DATE	1 J4


25/SEP/24

DUKE ENERCY	PROJECT DRAWING NUMBER	REV
DUKE ENERGY ENERGY KNIGHTDALE BATTERY ENERGY STORAGE SYSTEM	419596 KND01-CV-C-SI.CS-01	D
COVER SHEET	CODE	
5201 KNIGHTDALE EAGLE ROCK ROAD KNIGHTDALE, NC 27545	AREA	











7. PLACE BACKFILL AND FILL MATERIALS IN LAYERS NOT MORE THAN 8 INCHES IN LOOSE DEPTH FOR MATERIAL COMPACTED BY APPROPRIATE COMPACTION EQUIPMENT AND NOT MORE THAN 4 INCHES IN LOOSE DEPTH



 1
 2
 3
 4
 5
 6
 7
 8
 9
 10




RIPRAP SCHEDULE							
OUTLET	SHEET	L (FT)	T (FT)	W1 (FT)	W2 (FT)	D50 (FT)	REMARKS
BASIN OUTFALL	GR.PL-02	14	0.5	4.5	16.0	0.50.	
SWALE 1	GR.PL-01	8	0.5	3.0	9.0	5	
SWALE 2	GR.PL-02	14	0.5	4.0	16.0	0.5	



SECTION 2	
SEE THIS DWG	
NO SCALE	
	4" THICK #57 STONE
<u></u>	<u>*</u>
TYPICAL	12" THICK PREPARED
SECTION 3 - YARD SURFACING	SUBGRADE
SEE THIS DWG	
NO SCALE	
	6" THICK #57 STONE
	*
TYPICAL	12" THICK PREPARED
SUBSTATION SURFACING	SUBGRADE
SEE THIS DWG	
NO SCALE	

				DITO	CH SCHEDUL	E					
COORDINATES				LENGTH			CLODE				
DITCH NO.	STA	ART	EN	ID	LENGTH (FT)	START INV ELV	END INV ELEV	SLOPE (FT/FT)	LINING	DESIGN LIFE	REMARKS
	NORTHING	EASTING	NORTHING	EASTING	()			(,,			
S-1	741373.79	2161398.82	741481.42	2161843.09	518	327.15	319.19	VARIES		PERMANENT	OFFSITE DIVERSION
S-2	741336.08	2161426.57	740448.39	2161516.95	916	317.17	313.17	0.005	GRASS	PERMANENT	OFFSITE DIVERSION
S-3	741469.83	2161766.32	740851.99	2161706.11	736	320.67	305.46	0.005	GRASS	PERMANENT	CONVEYANCE
S-4A	740495.88	2161719.25	740649.74	2161713.76	110	316.20	315.82	0.003	GRASS	PERMANENT	CONVEYANCE
S-4B	740497.37	2161730.03	740650.30	2161739.52	44	311.87	305.38	0.237	RIPRAP	PERMANENT	CONVEYANCE
D-1	741471.43	2161846.77	740863.24	2161711.88	763	318.00	305.38	0.010	EC BLANKET	TEMPORARY	CONVEYANCE
D-2	740415.74	2161746.18	740204.10	2161744.09	212	309.00	303.00	0.005	EC BLANKET	TEMPORARY	OFFSITE DIVERSION



ISSUED FOR PERMITTING
THE DISTRIBUTION AND USE OF THE NATIVE FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST CONTROLLED VERSION.


SEAL 058674


SEAL USAGINEER COLLINIARION OF THE STATE OF

PΜ				D	25/SEP/2024	ISSUED FOR PERMITTING	сьс мімндирзьр
1:09				С	12/SEP/2024	ISSUED FOR PERMITTING	CLC MJMHGUDSLD
122				В	4/SEP/2024	ISSUED FOR 60% REVIEW	CLC MJMHGUDSLD
4/20				Α	22/AUG/2024	ISSUED FOR PERMIT	CLC MJMHUGDSLD -
2/17				NO	DATE	REVISIONS AND RECORD OF ISSUE	DRN DES CHK PDE APP

₽,	BLAC	K & VEATCH world of difference.	\$
DESIGNER	MIM	DRAWN CLC	

DUKE ENERGY	PROJECT DRAWING NUMBER	REV		
DUKE ENERGY ENERGY KNIGHTDALE BATTERY ENGERY STORAGE FACILITY	KND01-CV-C-GR.SD-01			
SURFACING DETAILS 5201 KNIGHTDALE EAGLE ROCK ROAD	CODE -			
KNIGHTDALE EAGLE ROCK ROAD KNIGHTDALE, NC 27545	AREA _			






1. INSTALL IMPERVIOUS GEOMEMBRANE PRIOR TO INSTALLING FILTER SOCKS.

2. INSTALL ON FLAT GRADE FOR OPTIMAL PERFORMANCE.

3. 18" DIAMETER FILTER SOCK MAY BE STACKED ONTO DOUBLE 24" DIAMETER SOCKS IN PYRAMIDAL CONFIGURATION FOR ADDED HEIGHT.

> COMPOST SOCK WASHOUT INSTALLATION DETAIL NOT TO SCALE



PLAN VIEW


- COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE SOCK SHALL BE EXTENDED AT LEAST 15 FEET UP SLOPE AT 45 DEGREES TO THE MAIN SOCK
- ALIGNMENT. TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE SOCK AND
- DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN. SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24
- HOURS OF INSPECTION. BIODEGRADABLE FILTER SOCK SHALL BE REPLACED AFTER 6 MONTHS, PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
- UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

COMPOST STANDARDS


ORGANIC MATTER CONTENT = 80%-100% (DRY WEIGHT BASIS) PARTICLE SIZE = 98% PASS THROUGH 1" SCREEN SOLUBLE SALT CONCENTRATION = 5.0 dS MAXIMUM ORGANIC PORTION = FIBROUS AND ELONGATED pH = 5.5 - 8.0MOISTURE CONTENT = 35% - 55%

COMPOST FILTER SOCK INSTALLATION DETAIL

NOT TO SCALE



- 1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED, NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
- 2. BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE BLANKET IN A 6" DEEP X 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE BLANKET.
- 3. ROLL CENTER BLANKET IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING OPTIONAL DOT SYSTEM TM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
- 4. PLACE CONSECUTIVE BLANKETS END OVER END (SHINGLE STYLE) WITH A 4"-6" OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" APART AND 4" ON CENTER TO SECURE BLANKETS.
- 5. FULL LENGTH EDGE OF BLANKETS AT TOP OF SIDE SLOPE MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN A 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
- 6. ADJACENT BLANKETS MUST BE OVERLAPPED APPROXIMATELY 2"-5" (DEPENDING ON BLANKET TYPE) AND STAPLED. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE BLANKET BEING OVERLAPPED.
- 7. IN HIGH FLOW CHANNEL APPLICATIONS, A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" APART AND 4" ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL
- 8. THE TERMINAL END OF THE BLANKETS MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN A 6" DEEP X 6" WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.



CRITICAL POINTS

A. OVERLAPS AND SEAMS B. PROJECTED WATER LINE C. CHANNEL BOTTOM/SIDE SLOPE VERTICES

* HORIZONTAL STAPLE SPACING SHOULD BE ALTERED IF NECESSARY TO ALLOW STAPLES TO SECURE THE CRITCAL POINTS ALONG THE CHANNEL SURFACE.

** IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY ANCHOR THE BLANKETS.

SC150 OR C125 EROSION BLANKET INSTALLATION (DITCH SLOPES ONLY)


NOT TO SCALE

CONSTRUCTION SEQUENCE

- EROSION CONTROL PLAN IS APPROVED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENTAL QUALITY (NCDEQ)
- 2. CONTRACTOR SHALL SUBMIT NOI TO NCDEQ FOR APPROVAL.
- ONCE THE CERTIFICATE OF COVERAGE IS RECEIVED FROM NCDEQ, THE LIMITS OF DISTURBANCE (LOD) SHALL BE FIELD MARKED PRIOR TO INSTALLATION OF SEDIMENT CONTROL MEASURES, OR OTHER LAND DISTURBING ACTIVITIES.
- 4. INSTALL STABILIZED CONSTRUCTION ENTRANCE.
- INSTALL PERIMETER FILTER SOCK PRIOR TO ANY OTHER LAND DISTURBING ACTIVITIES.
- PERFORM CLEARING AND GRUBBING AS REQUIRED AND INSTALL SEDIMENT BASIN AND EROSION CONTROL DITCHES, INCLUDING OUTLET PIPE AND RIPRAP
- PERFORM SITE CLEARING.

INSTALL DIVERSION DITCHES. ONCE ALL DIVERSION DITCHES HAVE BEEN INSTALLED, UPSLOPE FILTER SOCK SHALL NO LONGER BE REQUIRED. CONTRACTOR SHALL MAINTAIN DOWNSLOPE FILTER SOCK UNTIL FINAL STABILIZATION.

- 8. PERFORM MASS GRADING ACTIVITIES.
- UPON FINAL STABILIZATION RECEIVE FINAL APPROVAL FROM THE EROSION AND SEDIMENT CONTROL INSPECTOR. CONTRACTOR SHALL SUBMIT N.O.T. AFTER FINAL APPROVAL. ONCE N.O.T. IS APPROVED, CONTRACTOR SHALL REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES.



TYPICAL STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE

PROFILE

ISSUED FOR PERMITTING

THE DISTRIBUTION AND USE OF THE NATIVE FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST CONTROLLED VERSION.



DRAWING NUMBER

									_
									I
	С	25/SEP/2024	ISSUED FOR PERMITTING	CLC	MJM	HGU	DSLE		
	В	12/SEP/2024	ISSUED FOR PERMITTING	CLC	MJM	HGU)SLC	<u> </u>	
	Α	4/SEP/2024	ISSUED FOR 60% REVIEW	CLC	MJM	HGU)SLC	<u> </u>	
	NO	DATE	REVISIONS AND RECORD OF ISSUE	DRN	DES	СНК	PDE	ΑP	Ρ

R _®	BLA(Building	CK & VE	ATCH difference.®	V
DESIGNER		DRAWN		

25/SEP/24


DUKE ENERGY
ENERGY, KIGHTDALE BATTERY ENERGY STORAGE SYSTEM

INSTALLED IN ACCORDANCE WITH NCDOT

STANDARD SPECIFICATIONS SECTION 1056

419596 KND01-CV-C-EC.SD-01 **EROSION & SEDIMENT CONTROL DETAILS** 5201 KNIGHTDALE EAGEL ROCK ROAD KNIGHTDALE, NC 27544

PROJECT





419596 KND01-CV-C-EC.SD-02

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

mplementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

	Required Ground Stabilization Timeframes							
Si	te Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations					
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None					
(b)	High Quality Water (HQW) Zones	7	None					
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed					
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed					
(e)	Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope					

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Tamanavani	Caab:
Temporary	Stapi

- Temporary grass seed covered with straw or other mulches and tackifiers
- Hydroseeding

Plastic sheeting

- Rolled erosion control products with or without temporary grass seed
- Appropriately applied straw or other mulch

Permanent Stabilization Permanent grass seed covered with straw or

- other mulches and tackifiers Geotextile fabrics such as permanent soil
- reinforcement matting Hydroseeding
- Shrubs or other permanent plantings covered
- Uniform and evenly distributed ground cover sufficient to restrain erosion
- Structural methods such as concrete, asphalt or retaining walls
- Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- 1. Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- 2. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- 3. Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- 4. Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- 2. Provide drip pans under any stored equipment.
- 3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the
- 4. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem
- 6. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- 1. Never bury or burn waste. Place litter and debris in approved waste containers.
- 2. Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- 3. Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- 5. Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- 6. Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- 8. Dispose waste off-site at an approved disposal facility.
- 9. On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE

- 1. Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- 2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- 3. Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- 5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS

- 1. Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.


EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- 3. Provide stable stone access point when feasible.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.





CONCRETE WASHOUTS

- 1. Do not discharge concrete or cement slurry from the site.
- 2. Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- 3. Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- 4. Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- 5. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- 6. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- 8. Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- 9. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- 10. At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES. PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- 2. Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- 3. Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- 4. Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

- 1. Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.


EFFECTIVE: 04/01/19

ISSUED FOR PERMITTING

THE DISTRIBUTION AND USE OF THE NATIVE FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST CONTROLLED VERSION.



			С	25/SEP/2024	ISSUED FOR PERMITTING	CLC MJN	/HGUDSLD	
			В	12/SEP/2024	ISSUED FOR PERMITTING	CLC MJN	/HGUDSLD	
			Α	4/SEP/2024	ISSUED FOR 60% REVIEW	CLC MJN	/HGUDSLD	
			NO	DATE	REVISIONS AND RECORD OF ISSUE	DRN DES	CHK PDE	APP



DUKE ENERGY
ENERGY. KIGHTDALE BATTERY ENERGY STORAGE SYSTEM **EROSION & SEDIMENT CONTROL DETAILS** 5201 KNIGHTDALE EAGEL ROCK ROAD

KNIGHTDALE, NC 27544

DRAWING NUMBER 419596 KND01-CV-C-EC.DS-03

PART III

SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours	 Identification of the measures inspected, Date and time of the inspection, Name of the person performing the inspection, Indication of whether the measures were operating properly, Description of maintenance needs for the measure, Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDCs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 Identification of the discharge outfalls inspected, Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, Indication of visible sediment leaving the site, Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	 If visible sedimentation is found outside site limits, then a record of the following shall be made: Actions taken to clean up or stabilize the sediment that has left the site limits, Description, evidence, and date of corrective actions taken, and An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.
(6) Ground stabilization measures	After each phase of grading	 The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC measures.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation to be Kept on Site

In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- (a) This General Permit as well as the Certificate of Coverage, after it is received.
- (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years

All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- (a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items,
- (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit,
- (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,
- (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,
- (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- (f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION C: REPORTING

1. Occurrences that Must be Reported

Permittees shall report the following occurrences:

- (a) Visible sediment deposition in a stream or wetland.
- (b) Oil spills if:
 - They are 25 gallons or more,
- They are less than 25 gallons but cannot be cleaned up within 24 hours,
- They cause sheen on surface waters (regardless of volume), or
- They are within 100 feet of surface waters (regardless of volume).
- Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- (d) Anticipated bypasses and unanticipated bypasses.
- (e) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment	Within 24 hours, an oral or electronic notification.
deposition in a	Within 7 calendar days, a report that contains a description of the
stream or wetland	sediment and actions taken to address the cause of the deposition.
	Division staff may waive the requirement for a written report on a
	case-by-case basis.
	 If the stream is named on the NC 303(d) list as impaired for sediment-
	related causes, the permittee may be required to perform additional
	monitoring, inspections or apply more stringent practices if staff
	determine that additional requirements are needed to assure compliance
	with the federal or state impaired-waters conditions.
(b) Oil spills and	Within 24 hours, an oral or electronic notification. The notification
release of	shall include information about the date, time, nature, volume and
hazardous	location of the spill or release.
substances per Item	
1(b)-(c) above	
(c) Anticipated	 A report at least ten days before the date of the bypass, if possible.
bypasses [40 CFR	The report shall include an evaluation of the anticipated quality and
122.41(m)(3)]	effect of the bypass.
(d) Unanticipated	Within 24 hours, an oral or electronic notification.
bypasses [40 CFR	Within 7 calendar days, a report that includes an evaluation of the
122.41(m)(3)]	quality and effect of the bypass.
(e) Noncompliance	Within 24 hours, an oral or electronic notification.
with the conditions	Within 7 calendar days, a report that contains a description of the
of this permit that	noncompliance, and its causes; the period of noncompliance,
may endanger	including exact dates and times, and if the noncompliance has not
health or the	been corrected, the anticipated time noncompliance is expected to
environment[40	continue; and steps taken or planned to reduce, eliminate, and
CFR 122.41(I)(7)]	prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6).
	Division staff may waive the requirement for a written report on a
	- Division stan may warre the regularitement of a whiteen report on a



NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

ISSUED FOR PERMITTING

FORMAT CAD FILE OF THIS DRAWING IS UNCONTROLLED. THE USER SHALL VERIFY TRACEABILITY OF THIS DRAWING TO THE LATEST CONTROLLED VERSION.



₽M							
5:38				С	25/SEP/2024	ISSUED FOR PERMITTING	CLC MJMHGUDSLD
774				В	12/SEP/2024	ISSUED FOR PERMITTING	CLC MJMHGUDSLD
3/2024				А	4/SEP/2024	ISSUED FOR 60% REVIEW	CLC MJMHGUDSLD
8/23				NO	DATE	REVISIONS AND RECORD OF ISSUE	DRN DES CHK PDE APP

BLACK & VEATCH

Building a world of difference.

DUKE ENERGY
ENERGY. KIGHTDALE BATTERY ENERGY STORAGE SYSTEM

419596 KND01-CV-C-EC.DS-04

EROSION & SEDIMENT CONTROL DETAILS 5201 KNIGHTDALE EAGEL ROCK ROAD KNIGHTDALE, NC 27544

